


# Henry<sup>®</sup> Prodeq<sup>™</sup> System

## Submittal Packet



# Table of Contents

## Henry® Prodeq™ System

### Technical Data Sheets

#### Membrane

Henry® Prodeq™ FX 400 .....	3
-----------------------------	---

#### Primer Options

Henry® ST Primer .....	6
------------------------	---

Henry® LV Primer .....	9
------------------------	---

Henry® STXL Primer .....	12
--------------------------	----

#### Flashing Options

Henry® Prodeq FX 400 .....	15
----------------------------	----

Henry® Pumadeq™ Flex 31MV .....	18
---------------------------------	----

#### Wearcoat Option

Henry® GP Wearcoat .....	21
--------------------------	----

#### Topcoat Option

Henry® GP Topcoat .....	24
-------------------------	----

#### Accessories

Henry® FX Activator .....	27
---------------------------	----

### Safety Data Sheets

Henry® Prodeq™ FX 400 Part A .....	29
------------------------------------	----

Henry® Prodeq™ FX 400 Green Part B .....	38
--	----

Henry® Prodeq™ FX 400 Dark Grey Part B .....	46
--	----

### Architectural Details

Henry® Prodeq™ System - All Details .....	54
---	----

### Sample Warranty

Henry® Prodeq™ 5 Year Material Warranty .....	90
---	----

### Product Certification

Henry® Prodeq™ System Product Certification .....	92
---	----

### LEED Declarations

Henry® Prodeq™ FX 400 LEED Information .....	93
--	----



TECHNICAL DATA SHEET  
**Prodeq FX 400**

Spray Applied, Polyurethane Hybrid, Waterproofing Membrane

Physical property	Typical value	Test method
Appearance	Green, Gray	-
Solids Content by Volume	100%	ASTM D1644, Method A
Tensile Strength	1600 psi	C957/957M
Elongation	300%	C957/957M
Crack Bridging @ 100 mils	Pass	C1305
Hardness, Shore A	100	D2240
Hydrostatic Pressure Resistance	130 psi	D5385
Root Resistance	Pass	FLL
VOC Content (maximum)	0 g/l	-

### Description

**Henry® Prodeq FX 400** is a 100% solids, spray applied, polyurethane hybrid, waterproofing membrane that is instant setting. **Prodeq FX 400** is designed to provide seamless protection.

### Features

- Instant setting, even at low temperatures, eliminating the requirement for complicated, labor intensive detailing items
- Spray applied which greatly reduces labor time and cost
- Can be constantly submerged in water
- Hard wearing and durable, reducing damage on site
- No protection board or root barrier required
- Low odor, zero VOC, no solvents

### Usage

**Prodeq FX 400** is used as a waterproofing membrane for:

- Protected Membrane Roofing (PMR)
- Plaza Decks
- Inverted Roof Membrane Assemblies (IRMA)
- Green Roofs (VRA)
- Split Slabs
- Planters
- Terraces

### Application

**Site Conditions:** All surfaces should be prepared per the approved Henry specification and TechTalk. Surface temperature must be at least 5° F above the dew point and rising. Use a surface dew point meter. Air and substrate temperatures must be between 32° F and 100° F. Relative humidity must be less than 80%.

**Surface Prep:** Surfaces to be over-coated must be firm, dry and free of loose particles, such as sand in the primer, and contaminants that would impair adhesion.

If there are any doubts about suitability of a surface, further advice should be sought from a Henry representative and a small trial area should be applied and tested appropriately.

### Product Mixing: Prodeq FX 400

It is important that all material reaches the required temperature before spraying.

Pre-heat components using drum-pads and blanket heaters until pre-temperature gauge on machine reads 110° F.

## Henry FX400

---

Set pre-heaters at:

ISO = 170° F.

Polyol = 165° F minimum.

Set hoses at 160° F.

Pre-mix components using an agitator with special drum paddle attachment.

Use recycling block and circulate material back into drums for 30 minutes at the beginning of each day to ensure cold material in lines reaches the required temperature.

Part A – Isocyanate is a clear, translucent color

Part B – Polyol is green or gray (depending on membrane color choice)

When mixed, a homogenous, streak free green or gray colored membrane is formed

### Mix Ratio: 1 to 1, by volume

1 Part A – Isocyanate

1 Part B – Polyol

**Pot Life @ 68° F:** Not Applicable

**Product Application: FX 400** is only applied by plural component machinery.

Protect spray machine and **FX 400** drums from inclement weather.

Use AP52/52 to AP29/29 spray tip.

Consult the spray machine manufacturer for expert advice.

Always carry out spray trials before work proceeds.

Keep a small bucket beside spray operative to pre-spray into, ensuring proper mix, before application on substrate.

Protect hoses from abrasion on sanded primer. Be careful of loose hose protection fragments contaminating deck.

### Application Rate:

- Apply at a rate of approximately 1600 sf/kit. Allow for material wastage due to wind.

**WFT-DFT:** 100 mils on field – 140 mils on details and transitions, minimum.

### Re-coat and Traffic Times after application:

Minimum @ 68° F = 1 hour

Maximum 24 hours. When overlapping membrane after more than 24 hours, wipe with a clean cloth and **Henry FX Activator**.

Allow **FX Activator** to evaporate before over coating.

### Product Restrictions and Limitations:

Can be rained on after 1 minute.

Can be walked on after 10 minutes.

**NOTE:** Before using **FX 400**, please refer to Safety Data Sheet (SDS).

Always wear suitable, full protective clothing (hooded overalls), butyl rubber or nitrile gloves, durable footwear and safety goggles with side shields during mixing and application.

Ensure the same safe working methods are followed for all persons in the work area.

Follow guidelines in NIOSH alert concerning spraying MDI's, using properly trained operatives.

Provide ventilation in enclosed spaces and wear powered, air purifying respirator with helmet and full-face shield.

When **FX 400** is applied, wear NIOSH/MSHA approved (TC23 or TC-21/TC84A) respirators.

Observe OSHA regulations for respirator use (29 CFR 1910.134).

Uncured resins may be toxic. They may cause allergic reactions or hypersensitivity reactions.

Protect adjacent areas from overspray or other system-related contamination. Provide windbreaks where necessary.

Contact with skin – wash immediately with soap and water.

Contact with eyes – rinse immediately with lots of water and seek medical attention.

### Coverage

---

Application rates should be adjusted to meet each project's specified requirements. Coverage rates are theoretical and do not take into account material loss due to project conditions and working methods.

- For Henry System Warranty and Gold Seal Warranty requirements, refer to appropriate approved Henry specification for application and coverage rate requirements.

### Clean-up

---

Machine clean up should be done as per manufacturers' instructions.

Clean-up of tools may be accomplished by using Acetone or MEK.

Read and follow all Health and Safety instructions on SDS. Wash body with soap and water. Ensure all materials are mixed and cured before disposal, in accordance with federal, state, and local regulations. Dispose of all packaging in accordance with federal, state, and local regulations.

### Product contents / packaging size

---

FX 400 Part A	55 gal / 55 gal container
FX 400 Green Part B	55 gal / 55 gal container
FX 400 Dark Grey Part B	55 gal / 55 gal container

### Storage

---

It is important that these guidelines are also followed for drums that are being used while applying material.

In original, unopened containers store between 50° F and 80° F.

Storing the material at a higher temperature may reduce its shelf life.

Store under dry, ventilated conditions and out of direct sunlight. Keep in an upright position and do not over stack.

Do not allow water into drums.

Both Polyol and Isocyanate components are moisture sensitive and will absorb or react with atmospheric or liquid water.

Ensure there is no condensation or water around the top of the drum that may get in when drum bung holes are opened.

After use, partially filled drums should be purged of air using dry nitrogen spray.

This prevents the liquids (especially Part A, Isocyanate) from reacting with water in the air and solidifying.

Materials in machine should be sealed.

Before storing machines, consult machine manufacturer.

For more information, visit [www.henry.com](http://www.henry.com) or for technical assistance call us at 800-486-1278. For more information on the Henry® product warranty and liability disclaimer please visit [www.henry.com/warranty](http://www.henry.com/warranty). Refer to the Safety Data Sheet prior to using this product. The Safety Data Sheet is available at [www.henry.com](http://www.henry.com) or by emailing Henry® Product Support at [productsupport@henry.com](mailto:productsupport@henry.com) or by calling 800-486-1278.

Henry is a registered trademark of Henry Company.  
Covered by US patent 6,901,712; Canadian patent 2,413,550.

The technical and application information herein is based on the present state of our best scientific and practical knowledge. As the information herein is of a general nature, no assumption can be made as to a product's suitability for a particular use or application and no warranty as to its accuracy, reliability or completeness either expressed or implied is given other than those required by law. The user is responsible for checking the suitability of products for their intended use. Henry® Company data sheets are updated on a regular basis; it is the user's responsibility to obtain and to confirm the most recent version. Information contained in this data sheet may change without notice.

Physical property	Typical value	Test method
Appearance	Clear/Amber	-
Solids Content by Volume	100%	ASTM D1644-2001, Method A
Viscosity @ 68F, mixed	1050cps	ASTM D2196-10
Adhesion	> 435 psi, substrate failure	C1583/C1583M-04
VOC Content (maximum)	0 g/l	ASTM C1250-05

### Description

Henry® ST Primer is a 100% solids, two-component, epoxy primer.

### Features

- Designed to provide a thick resin film, capable of holding aggregate,
- Also fills cracks and small pores in surfaces
- Low odor, solvent free and VOC compliant
- After fully cured, can be left exposed to rain and ponded water

### Usage

ST Primer is used as a primer on concrete, wood, exterior cover/cement boards and steel.

### Application

**Site Conditions:** All surfaces should be prepared per the approved Henry specification and Tech Talk. Air and substrate temperatures must be between 50° F and 90° F. For temperatures below 50° F, use Henry® STXL Primer. Concrete must be cured for a minimum of 28 days.

**Surface Prep:** Substrates to be coated must be free of laitance and contaminants that would impair adhesion.

Do not apply on substrate that has been treated with any type of form release agent or sealer.

- Concrete should be shot blasted or mechanically abraded
- Surface profile must meet CSP 3-4
- Steel should be mechanically abraded by power tool (i.e. disc grinder or wire cup brush) in accordance with SSPC – SP3. Remove oil and other residue by wiping with MEK or Acetone and a clean cloth. Prime immediately after surface preparation to avoid flash rusting.
- Wood or Roof boards must be exterior grade, dry, clean and fixed with exterior screws

**Application:** Apply ST Primer when temperatures are constant or falling and out of direct sunlight, to minimize the risk of pinholes, blister formation or delamination due to moisture drive.

If there are any doubts about the suitability of a substrate, further advice should be sought from a Henry representative and a small trial area applied and tested appropriately.

**Product Mixing:** ST Primer Parts A (2 gallons) & B (1 gallon) are pre-measured.

Mix all Part A with all of Part B.

They must be thoroughly mixed, using an electric, slow speed (300-400rpm), high torque drill with spiral (Jiffy) mixing paddle.

### Mix Ratio by Volume:

1. Dispense Part A into a separate, clean, dry mixing pail. Mix for 30 seconds, taking care not to hit the sides.
2. Add Part B, taking care not to hit the sides, and mix for a minimum 1 minute.

Work the mixing paddle around the sides and bottom of the mixing pail to achieve a uniform, streak free, homogenous liquid. Scrape out all the material from the mixing pail. Decant to a new pail and use immediately

Do not mix new material with old, uncured material as this can significantly reduce work times. Use new pails frequently.

## Henry ST Primer

---

**Pot Life @ 68° F: 20 minutes.** The working time of **ST Primer** will be influenced by the length of time it is mixed (longer mixing results in shorter pot life), the substrate and ambient temperatures and how quickly it is removed from the mixing pail and spread on the substrate.

**Product Application: ST Primer** is applied evenly by a flat squeegee and back rolled with a medium nap (3/8") roller. Apply slight pressure on the roller to ensure all voids and pores are filled and remove all material puddles.

Broadcast clean, dry aggregate into wet resin as per Henry specification, typically sieve size #20-50 @ 0.25lbs/sf

### Application Rate:

- 135sq.ft/gal (400sq.ft/3-gal. kit) on CSP 3-4 profile substrate

Allow for saturation of rollers and brushes

**WFT-DFT:** 10 mils, depending on surface porosity

### Re-coat and Traffic Times after application:

Minimum @ 68° F = 4 hours.

Maximum 48 hours.

No maximum when fully broadcast with sand.

If this maximum time is exceeded, **ST Primer** must be abraded (to a dull finish), wiped with Acetone or MEK and clean cloths.

### Product Restrictions and Limitations:

**ST Primer** will not bridge cracks or joints in the substrate.

Cannot prevent moisture mitigation – use **Henry® GC** or **Henry® GCXL Primer**

It cannot be used for aluminum, copper, brass or galvanized metals. Use **Henry® Pumadeq Primer 20**.

It can be rained on 4 hours after installation @ 68 F. Colder temperatures will increase this time.

If ST Primer gets wet during cure (rain, dew or fog), the surface will “bloom”, evidenced by white spots that must be ground off.

It must then be re-applied.

**NOTE:** Before using **ST Primer**, please refer to Safety Data Sheet (SDS). Ensure the same safe working methods are followed for all persons in the work area. Wear suitable protective clothing, butyl rubber or nitrile gloves, and safety goggles with side shields during mixing and application.

When **ST Primer** is applied in enclosed areas without natural ventilation, forced ventilation must be arranged. Avoid strong concentration of vapor as well as direct contact with skin or eyes.

If concentration exceeds recommended limits in SDS, a NIOSH approved respirator (OSHA 29 CFR 1910.134) is required.

Avoid direct contact with skin or eyes.

Uncured epoxies are corrosive, toxic or both. They may cause allergic reactions or hypersensitivity reactions.

Contact with skin – wash immediately with soap and water

Contact with eyes – rinse immediately with lots of water and seek medical attention

## Coverage

---

Application rates should be adjusted to meet each project's specified requirements. Coverage rates are theoretical and do not take into account material loss due to surface porosity, project conditions and working methods.

- For Henry System Warranty and Gold Seal Warranty requirements, refer to appropriate approved Henry specification for application and coverage rate requirements.

## Clean-up

---

Clean-up of tools and equipment may be accomplished by using Acetone or MEK. Read and follow all Health and Safety instructions on SDS. Wash body with soap and water. Ensure all materials are mixed and cured before disposal, in accordance with federal, state, and local regulations. Dispose of all packaging in accordance with federal, state, and local regulations.

## Product contents / packaging size

---

Part A 2 gal / 2 gal container

Part B 1 gal / 1 gal container

**Storage**

---

One year in unopened containers stored between 50° F and 80° F under dry, ventilated conditions, and out of direct sunlight. Storing the material at a higher temperature may reduce its shelf life. Keep in an upright position and do not over stack.

For more information, visit [www.henry.com](http://www.henry.com) or for technical assistance call us at 800-486-1278. For more information on the Henry® product warranty and liability disclaimer please visit [www.henry.com/warranty](http://www.henry.com/warranty). Refer to the Safety Data Sheet prior to using this product. The Safety Data Sheet is available at [www.henry.com](http://www.henry.com) or by emailing Henry® Product Support at [productsupport@henry.com](mailto:productsupport@henry.com) or by calling 800-486-1278.

Henry is a registered trademark of Henry Company.  
Covered by US patent 6,901,712; Canadian patent 2,413,550.

The technical and application information herein is based on the present state of our best scientific and practical knowledge. As the information herein is of a general nature, no assumption can be made as to a product's suitability for a particular use or application and no warranty as to its accuracy, reliability or completeness either expressed or implied is given other than those required by law. The user is responsible for checking the suitability of products for their intended use. Henry® Company data sheets are updated on a regular basis; it is the user's responsibility to obtain and to confirm the most recent version. Information contained in this data sheet may change without notice.



Physical property	Typical value	Test method
Appearance	Clear	-
Solids Content by Volume	100%	ASTM D1644-2001, Method A
Viscosity @ 68 F	400 cps	D2196-10
Adhesion	> 435 psi, substrate failure	C1583/C1583M-04
VOC Content (maximum)	0 g/l	ASTM C1250-05

## Description

Henry® LV Primer is a 100% solids, two-component, low viscosity, epoxy primer.

## Features

- Used to prime surfaces before further resin application
- Also fills cracks and small pores in surfaces
- Low odor, solvent free and VOC compliant
- After fully cured, can be left exposed to rain and ponded water

## Usage

LV Primer is used as a primer on concrete, wood, exterior cover/cement boards and steel.

## Application

**Site Conditions:** All surfaces should be prepared per the approved Henry specification and Tech Talk.

Air and substrate temperatures must be between 50° F and 90° F.

The surface temperature must be at least 5° F above the dew point and rising. Use a surface dew point meter.

Concrete must be cured a minimum of 28 days.

**Surface Prep:** Substrates to be coated must be free of laitance and contaminants that would impair adhesion.

Do not apply on substrate that has been treated with any type of form release agent or sealer.

- Concrete should be shot blasted or mechanically abraded
- Surface profile must meet CSP 3-4
- Wood and exterior cement or cover boards must be exterior grade, dry, clean and fixed with exterior screws

**Application:** LV Primer should be applied out of direct sunlight and when temperatures are falling to minimize the risk of pinholes due to moisture drive. If there are any doubts about the suitability of a substrate, further advice should be sought from a Henry representative and a small trial area applied and tested appropriately.

**Product Mixing:** LV Primer Parts A & B are pre-measured.

Mix all Part A with all of Part B.

They must be thoroughly mixed, using an electric, slow speed (300-400rpm), high torque drill with spiral (Jiffy) mixing paddle.

### Mix Ratio by Volume:

1. Dispense Part A into a separate, clean, dry mixing pail. Mix for 30 seconds, taking care not to hit the sides.
2. Add Part B, taking care not to hit the sides, and mix for a minimum 1 minute.

Work the mixing paddle around the sides and bottom of the mixing pail to achieve a uniform, streak free, homogenous liquid.

Scrape out all the material from the mixing pail. Decant to a new pail and use immediately.

Do not mix new material with old, uncured material as this can significantly reduce work times. Use new pails frequently.

## Henry LV Primer

---

**Pot Life @ 68° F: 20 minutes.** The working time of **LV Primer** will be influenced by the length of time it is mixed (longer mixing results in shorter pot life), the substrate and ambient temperatures and how quickly it is removed from the mixing pail and spread on the substrate.

**Product Application:** **LV Primer** is applied evenly by a flat squeegee and back rolled with a medium nap (3/8") roller. Apply slight pressure on the roller to ensure all voids and pores are filled and remove all material puddles.

**Application Rate:**

- 200 – 300 sq/ft gal (600 – 900 sf/3 gal kit), on CSP 3-4 profile substrate

Allow for saturation of rollers and brushes

**WFT-DFT:** 5-8 mils, depending on surface porosity

**Re-coat and Traffic Times after application:**

Minimum @ 68° F = 8 hours.

Maximum @ 68° F = 24 hours.

Colder temperatures will increase this time.

If this maximum time is exceeded, **LV Primer** must be wiped with a clean cloth and MEK. It may require light abrasion.

**Product Restrictions and Limitations:**

**LV Primer** will not bridge cracks or joints in the substrate.

Cannot prevent moisture mitigation – use **Henry® GC Primer** or **Henry® GCXL Primer**.

It cannot be used for aluminum, copper, brass or galvanized metals. Use **Henry® Pumadeq Primer 20**.

It can be rained on 8 hours after installation @ 68° F. Colder temperatures will increase this time.

If **LV Primer** gets wet during cure (rain, dew or fog), the surface will “bloom”, evidenced by white spots that must be ground off.

It must then be re-applied.

**NOTE:** Before using **LV Primer**, please refer to Safety Data Sheet (SDS). Ensure the same safe working methods are followed for all persons in the work area. Wear suitable protective clothing, butyl rubber or nitrile gloves, and safety goggles with side shields during mixing and application.

Respiratory makes should be worn at all times when adequate ventilation does not exist.

A NIOSH/MSHA (TC-23C-1809), multi gas vapor respirator is acceptable.

Avoid direct contact with skin or eyes.

Uncured epoxies are corrosive, toxic or both. They may cause allergic reactions or hypersensitivity reactions.

Contact with skin – wash immediately with soap and water.

Contact with eyes – rinse immediately with lots of water and seek medical attention.

## Coverage

---

Application rates should be adjusted to meet each project's specified requirements. Coverage rates are theoretical and do not take into account material loss due to surface porosity, project conditions and working methods.

- For Henry System Warranty and Gold Seal Warranty requirements, refer to appropriate approved Henry specification for application and coverage rate requirements.

## Clean-up

---

Clean-up of tools and equipment may be accomplished by using Acetone or MEK. Read and follow all Health and Safety instructions on SDS. Wash body with soap and water. Ensure all materials are mixed and cured before disposal, in accordance with federal, state, and local regulations. Dispose of all packaging in accordance with federal, state, and local regulations.

## Product contents / packaging size

---

Part A 4 gal / 4 gal container

Part B 1 gal / 1 gal container

## Henry LV Primer

---

### Storage

---

One year in unopened containers stored between 50° F and 80° F under dry, ventilated conditions, and out of direct sunlight. Storing the material at a higher temperature may reduce its shelf life. Keep in an upright position and do not over stack.

For more information, visit [www.henry.com](http://www.henry.com) or for technical assistance call us at 800-486-1278. For more information on the Henry® product warranty and liability disclaimer please visit [www.henry.com/warranty](http://www.henry.com/warranty). Refer to the Safety Data Sheet prior to using this product. The Safety Data Sheet is available at [www.henry.com](http://www.henry.com) or by emailing Henry® Product Support at [productsupport@henry.com](mailto:productsupport@henry.com) or by calling 800-486-1278.

Henry is a registered trademark of Henry Company.  
Covered by US patent 6,901,712; Canadian patent 2,413,550.

The technical and application information herein is based on the present state of our best scientific and practical knowledge. As the information herein is of a general nature, no assumption can be made as to a product's suitability for a particular use or application and no warranty as to its accuracy, reliability or completeness either expressed or implied is given other than those required by law. The user is responsible for checking the suitability of products for their intended use. Henry® Company data sheets are updated on a regular basis; it is the user's responsibility to obtain and to confirm the most recent version. Information contained in this data sheet may change without notice.



Physical property	Typical value	Test method
Appearance	Clear/Amber	-
Solids Content by Volume	100%	ASTM D1644-2001, Method A
Viscosity @ 68F, mixed	1050cps	ASTM D2196-10
Adhesion	> 435 psi, substrate failure	C1583/C1583M-04
VOC Content (maximum)	0 g/l	ASTM C1250-05

## Description

Henry® STXL Primer is a low temperature, fast curing, 100% solids, two-component, epoxy primer.

## Features

- It is used when application temperatures below 50° F, or if faster (than **ST Primer**) cure times are required.
- Designed to provide a thick resin film, capable of holding aggregate,
- Also fills cracks and small pores in surfaces
- Low odor, solvent free and VOC compliant
- After fully cured, can be left exposed to rain and ponded water

## Usage

STXL Primer is used as a primer on concrete, wood, exterior cover/cement boards and steel

## Application

**Site Conditions:** All surfaces should be prepared per the approved Henry specification and Tech Talk. Air and substrate temperatures must be between 40° F and 90° F. Concrete must be cured a minimum 28 days.

**Surface Prep:** Substrates to be coated must be free of laitance and contaminants that would impair adhesion. Do not apply on substrate that has been treated with any type of form release agent or sealer.

- Concrete should be shot blasted or mechanically abraded
- Surface profile must meet CSP 3-4
- Do not acid etch
- Steel should be mechanically abraded by power tool (i.e. disc grinder or wire cup brush) in accordance with SSPC – SP3. Remove oil and other residue by wiping with MEK or Acetone and a clean cloth Prime immediately after surface preparation to avoid flash rusting
- Wood or Roof Boards must be exterior grade, dry, clean and fixed with exterior screws

**Application:** Apply **STXL Primer** when temperatures are constant or falling and out of direct sunlight, to minimize the risk of pinholes, blister formation or delamination due to moisture drive. If there are any doubts about the suitability of a substrate, further advice should be sought from a Henry representative and a small trial area applied and tested appropriately.

**Product Mixing:** STXL Primer Parts A (2 gallons) & B (1 gallon) are pre-measured.

Mix all Part A with all of Part B

They must be thoroughly mixed, using an electric, slow speed (300-400rpm), high torque drill with spiral (Jiffy) mixing paddle.

### Mix Ratio by Volume:

1. Dispense Part A into a separate, clean, dry mixing pail. Mix for 30 seconds, taking care not to hit the sides.
2. Add Part B, taking care not to hit the sides, and mix for a minimum 1 minute.

Work the mixing paddle around the sides and bottom of the mixing pail to achieve a uniform, streak free, homogenous liquid. Scrape out all the material from the mixing pail. Decant to a new pail and use immediately. Do not mix new material with old, uncured material as this can significantly reduce work times. Use new pails frequently.

## Henry STXL Primer

---

**Pot Life @ 68° F: 15 minutes.** The working time of **STXL Primer** will be influenced by the length of time it is mixed (longer mixing results in shorter pot life), the substrate and ambient temperatures and how quickly it is removed from the mixing pail and spread on the substrate.

**Product Application:** **STXL Primer** is applied evenly by a flat squeegee and back rolled with a medium nap (3/8") roller. Apply slight pressure on the roller to ensure all voids and pores are filled and remove all material puddles.

Broadcast clean, dry aggregate into wet resin as per Henry specification, typically sieve size #20-50 @ 0.25lbs/sf

### Application Rate:

- 135sq.ft/gal (400sq.ft/3-gal. kit) on CSP 3-4 profile substrate

Allow for saturation of rollers and brushes

**WFT-DFT:** 10 mils, depending on surface porosity

### Re-coat and Traffic Times after application:

Minimum @ 40° F = 18 hours

Maximum 48 hours.

No maximum when fully broadcast with sand

**STXL Primer** can be used for faster cure times at lower temperatures

If this maximum overcoat time is exceeded, **ST Primer** must be abraded (to a dull finish), wiped with Acetone or MEK and clean cloths.

### Product Restrictions and Limitations:

**STXL Primer** will not bridge cracks or joints in the substrate.

Cannot prevent moisture mitigation – use **Henry® GC Primer** or **Henry® GCXL Primer**

It cannot be used for aluminum, copper, brass or galvanized metals. Use **Henry® Pumadeq Primer 20**.

It can be rained on 18 hours after installation @ 40° F. Colder temperatures will increase this time.

If **STXL Primer** gets wet during cure (rain, dew or fog), the surface will "bloom", evidenced by white spots that must be ground off.

It must then be re-applied.

**NOTE:** Before using **STXL Primer**, please refer to Safety Data Sheet (SDS). Ensure the same safe working methods are followed for all persons in the work area. Wear suitable protective clothing, butyl rubber or nitrile gloves, and safety goggles with side shields during mixing and application.

When **STXL Primer** is applied in enclosed areas without natural ventilation, forced ventilation must be arranged. Avoid strong concentration of vapor as well as direct contact with skin or eyes.

If concentration exceeds recommended limits in SDS, a NIOSH approved respirator (OSHA 29 CFR 1910.134) is required.

Avoid direct contact with skin or eyes.

Uncured epoxies are corrosive, toxic or both. They may cause allergic reactions or hypersensitivity reactions.

Contact with skin – wash immediately with soap and water

Contact with eyes – rinse immediately with lots of water and seek medical attention

## Coverage

---

Application rates should be adjusted to meet each project's specified requirements. Coverage rates are theoretical and do not take into account material loss due to surface porosity, project conditions and working methods.

- For Henry System Warranty and Gold Seal Warranty requirements, refer to appropriate approved Henry specification for application and coverage rate requirements.

## Clean-up

---

Clean-up of tools and equipment may be accomplished by using Acetone or MEK. Read and follow all Health and Safety instructions on SDS. Wash body with soap and water. Ensure all materials are mixed and cured before disposal, in accordance with federal, state, and local regulations. Dispose of all packaging in accordance with federal, state, and local regulations.

## Product contents / packaging size

---

Part A 2 gal / 2 gal container

Part B 1 gal / 1 gal container

### Storage

---

One year in unopened containers stored between 50° F and 80° F under dry, ventilated conditions, and out of direct sunlight. Storing the material at a higher temperature may reduce its shelf life. Keep in an upright position and do not over stack.

For more information, visit [www.henry.com](http://www.henry.com) or for technical assistance call us at 800-486-1278. For more information on the Henry® product warranty and liability disclaimer please visit [www.henry.com/warranty](http://www.henry.com/warranty). Refer to the Safety Data Sheet prior to using this product. The Safety Data Sheet is available at [www.henry.com](http://www.henry.com) or by emailing Henry® Product Support at [productsupport@henry.com](mailto:productsupport@henry.com) or by calling 800-486-1278.

Henry is a registered trademark of Henry Company.  
Covered by US patent 6,901,712; Canadian patent 2,413,550.

The technical and application information herein is based on the present state of our best scientific and practical knowledge. As the information herein is of a general nature, no assumption can be made as to a product's suitability for a particular use or application and no warranty as to its accuracy, reliability or completeness either expressed or implied is given other than those required by law. The user is responsible for checking the suitability of products for their intended use. Henry® Company data sheets are updated on a regular basis; it is the user's responsibility to obtain and to confirm the most recent version. Information contained in this data sheet may change without notice.



TECHNICAL DATA SHEET  
**Prodeq FX 400**

Spray Applied, Polyurethane Hybrid, Waterproofing Membrane

Physical property	Typical value	Test method
Appearance	Green, Gray	-
Solids Content by Volume	100%	ASTM D1644, Method A
Tensile Strength	1600 psi	C957/957M
Elongation	300%	C957/957M
Crack Bridging @ 100 mils	Pass	C1305
Hardness, Shore A	100	D2240
Hydrostatic Pressure Resistance	130 psi	D5385
Root Resistance	Pass	FLL
VOC Content (maximum)	0 g/l	-

### Description

**Henry® Prodeq FX 400** is a 100% solids, spray applied, polyurethane hybrid, waterproofing membrane that is instant setting. **Prodeq FX 400** is designed to provide seamless protection.

### Features

- Instant setting, even at low temperatures, eliminating the requirement for complicated, labor intensive detailing items
- Spray applied which greatly reduces labor time and cost
- Can be constantly submerged in water
- Hard wearing and durable, reducing damage on site
- No protection board or root barrier required
- Low odor, zero VOC, no solvents

### Usage

**Prodeq FX 400** is used as a waterproofing membrane for:

- Protected Membrane Roofing (PMR)
- Plaza Decks
- Inverted Roof Membrane Assemblies (IRMA)
- Green Roofs (VRA)
- Split Slabs
- Planters
- Terraces

### Application

**Site Conditions:** All surfaces should be prepared per the approved Henry specification and TechTalk. Surface temperature must be at least 5° F above the dew point and rising. Use a surface dew point meter. Air and substrate temperatures must be between 32° F and 100° F. Relative humidity must be less than 80%.

**Surface Prep:** Surfaces to be over-coated must be firm, dry and free of loose particles, such as sand in the primer, and contaminants that would impair adhesion.

If there are any doubts about suitability of a surface, further advice should be sought from a Henry representative and a small trial area should be applied and tested appropriately.

### Product Mixing: Prodeq FX 400

It is important that all material reaches the required temperature before spraying.

Pre-heat components using drum-pads and blanket heaters until pre-temperature gauge on machine reads 110° F.

## Henry FX400

---

Set pre-heaters at:

ISO = 170° F.

Polyol = 165° F minimum.

Set hoses at 160° F.

Pre-mix components using an agitator with special drum paddle attachment.

Use recycling block and circulate material back into drums for 30 minutes at the beginning of each day to ensure cold material in lines reaches the required temperature.

Part A – Isocyanate is a clear, translucent color

Part B – Polyol is green or gray (depending on membrane color choice)

When mixed, a homogenous, streak free green or gray colored membrane is formed

### Mix Ratio: 1 to 1, by volume

1 Part A – Isocyanate

1 Part B – Polyol

**Pot Life @ 68° F:** Not Applicable

**Product Application: FX 400** is only applied by plural component machinery.

Protect spray machine and **FX 400** drums from inclement weather.

Use AP52/52 to AP29/29 spray tip.

Consult the spray machine manufacturer for expert advice.

Always carry out spray trials before work proceeds.

Keep a small bucket beside spray operative to pre-spray into, ensuring proper mix, before application on substrate.

Protect hoses from abrasion on sanded primer. Be careful of loose hose protection fragments contaminating deck.

### Application Rate:

- Apply at a rate of approximately 1600 sf/kit. Allow for material wastage due to wind.

**WFT-DFT:** 100 mils on field – 140 mils on details and transitions, minimum.

### Re-coat and Traffic Times after application:

Minimum @ 68° F = 1 hour

Maximum 24 hours. When overlapping membrane after more than 24 hours, wipe with a clean cloth and **Henry FX Activator**.

Allow **FX Activator** to evaporate before over coating.

### Product Restrictions and Limitations:

Can be rained on after 1 minute.

Can be walked on after 10 minutes.

**NOTE:** Before using **FX 400**, please refer to Safety Data Sheet (SDS).

Always wear suitable, full protective clothing (hooded overalls), butyl rubber or nitrile gloves, durable footwear and safety goggles with side shields during mixing and application.

Ensure the same safe working methods are followed for all persons in the work area.

Follow guidelines in NIOSH alert concerning spraying MDI's, using properly trained operatives.

Provide ventilation in enclosed spaces and wear powered, air purifying respirator with helmet and full-face shield.

When **FX 400** is applied, wear NIOSH/MSHA approved (TC23 or TC-21/TC84A) respirators.

Observe OSHA regulations for respirator use (29 CFR 1910.134).

Uncured resins may be toxic. They may cause allergic reactions or hypersensitivity reactions.

Protect adjacent areas from overspray or other system-related contamination. Provide windbreaks where necessary.

Contact with skin – wash immediately with soap and water.

Contact with eyes – rinse immediately with lots of water and seek medical attention.



### Coverage

---

Application rates should be adjusted to meet each project's specified requirements. Coverage rates are theoretical and do not take into account material loss due to project conditions and working methods.

- For Henry System Warranty and Gold Seal Warranty requirements, refer to appropriate approved Henry specification for application and coverage rate requirements.

### Clean-up

---

Machine clean up should be done as per manufacturers' instructions.

Clean-up of tools may be accomplished by using Acetone or MEK.

Read and follow all Health and Safety instructions on SDS. Wash body with soap and water. Ensure all materials are mixed and cured before disposal, in accordance with federal, state, and local regulations. Dispose of all packaging in accordance with federal, state, and local regulations.

### Product contents / packaging size

---

FX 400 Part A	55 gal / 55 gal container
FX 400 Green Part B	55 gal / 55 gal container
FX 400 Dark Grey Part B	55 gal / 55 gal container

### Storage

---

It is important that these guidelines are also followed for drums that are being used while applying material.

In original, unopened containers store between 50° F and 80° F.

Storing the material at a higher temperature may reduce its shelf life.

Store under dry, ventilated conditions and out of direct sunlight. Keep in an upright position and do not over stack.

Do not allow water into drums.

Both Polyol and Isocyanate components are moisture sensitive and will absorb or react with atmospheric or liquid water.

Ensure there is no condensation or water around the top of the drum that may get in when drum bung holes are opened.

After use, partially filled drums should be purged of air using dry nitrogen spray.

This prevents the liquids (especially Part A, Isocyanate) from reacting with water in the air and solidifying.

Materials in machine should be sealed.

Before storing machines, consult machine manufacturer.

For more information, visit [www.henry.com](http://www.henry.com) or for technical assistance call us at 800-486-1278. For more information on the Henry® product warranty and liability disclaimer please visit [www.henry.com/warranty](http://www.henry.com/warranty). Refer to the Safety Data Sheet prior to using this product. The Safety Data Sheet is available at [www.henry.com](http://www.henry.com) or by emailing Henry® Product Support at [productsupport@henry.com](mailto:productsupport@henry.com) or by calling 800-486-1278.

Henry is a registered trademark of Henry Company.  
Covered by US patent 6,901,712; Canadian patent 2,413,550.

The technical and application information herein is based on the present state of our best scientific and practical knowledge. As the information herein is of a general nature, no assumption can be made as to a product's suitability for a particular use or application and no warranty as to its accuracy, reliability or completeness either expressed or implied is given other than those required by law. The user is responsible for checking the suitability of products for their intended use. Henry® Company data sheets are updated on a regular basis; it is the user's responsibility to obtain and to confirm the most recent version. Information contained in this data sheet may change without notice.



TECHNICAL DATA SHEET  
**Pumadeq™ Flex 31MV**  
Cold Fluid-Applied, PUMA, Reinforced, Flashing Membrane

Physical Property	Typical Value	Test Method
Appearance	White	-
Application Temperature (Ambient)	20 °F to 90 °F (-6 °C to 32 °C), can be lower	-
Abrasion Resistance	64mg	ASTM C501-84 (2009) - C17 wheel, 1000 grams, 1000 cycles
Hardness	35, Shore D	ASTM C2240-05 (as per C836M-10)
Solids Content by Volume	100%	ASTM D1644-2001 Method A
Adhesion	> 425 psi, substrate failure	ASTM C1583/ ASTM C1583M-04
Tensile Strength	1680 psi	ASTM D638-08
Elongation	283%	ASTM D638-08
VOC Content (maximum)	0 g/l	ASTM C1250-05

### Description

**Henry® Pumadeq™ Flex 31MV** (medium viscosity) is an elastic, viscous, waterproofing membrane based on polyurethane methyl methacrylate (PUMA) technology. Pumadeq technology combines the speed of PMMA technology in its application, with the elasticity of polyurethane technology. PUMA technology exhibits much greater elongation and flexibility than PMMA technology. **Pumadeq Flex 31MV** can be applied to vertical and horizontal surfaces as a flashing membrane.

### Features

- Cures within 1 hour, including temperatures below 40 °F (4 °C)
- Abrasion, Puncture, and UV Resistant
- Superior Elasticity vs PMMA technology
- Solvent-Free
- No VOC's

### Usage

**Pumadeq Flex 31MV** forms a waterproofing flashing membrane in the **Henry® Pumadeq System**. **Pumadeq System** applications:

- Protected Membrane Roofing
- IRMA
- Plaza Decks
- Green Roofs
- Split Slabs
- Parking Decks
- Balconies and Walkways
- Water Retention

### Application

**Site conditions:** Provide odor control, including air fans and exhausts.

Seal air intakes ,with activated carbon filters, nearby windows and doors.

Ensure a constant supply of "fresh air", required to remove monomers (heavier than air) from the resin surface and allow for cure.

**Surface preparation:** All surfaces should be prepared as per the approved **Pumadeq System** specification.

The surface temperature must be at least 5 °F (-15 °C) above the dew point and rising. Use a surface dew point meter.

Air and surface temperatures must be between 20 °F (-7 °C) and 90 °F (32 °C).

For temperatures below 40 °F (4 °C) consult Henry Product Support: 800-486-1278

Any surface or previous application of the **Pumadeq membrane** must be free of dust and contaminants that would impair adhesion

## Pumadeq™ Flex 31MV

---

of **Pumadeq Flex 31MV**. If the surface is contaminated or overcoat times between Pumadeq resins exceed 48 hours, wipe with **Pumadeq Cleaning Fluid** and clean cloths. After **Pumadeq Cleaning Fluid** evaporates (15 minutes), apply **Pumadeq Flex 31MV** within 1 hour or re-apply **Pumadeq Cleaning Fluid**.

If there are any doubts about the suitability of a substrate, further advice should be sought from Henry® Product Support and a small trial area applied and tested appropriately.

**Product mixing:** Prior to using **Pumadeq Flex 31MV**, it must be thoroughly mixed, using an electric, slow speed (300-400rpm), high torque drill with a clean, spiral, mixing paddle (Jiffy type, sized according to material amount mixed), to achieve a uniform distribution of the catalyst and paraffin contained in the product.

Only catalyze the amount of material that can be applied within the estimated pot life (10-15 minutes). Be aware that temperature conditions vary in areas of project and at different times of day. Adjust catalyst accordingly.

It is recommended to start by catalyzing 1 gallon of **Pumadeq Flex 31MV** to determine pot life.

- 1) Pre-mix **Pumadeq Flex 31MV** for minimum 1 minute
- 2) Then mix resin together with **Henry® Pumadeq Catalyst**, for 1 minute minimum  
A 1 volume oz. scoop is provided with each pail of catalyst
- 3) **Pumadeq Catalyst volume is noted below and is determined by the average of three temperatures: Pumadeq Flex 31MV temperature, ambient temperature, and substrate temperature.**

At temperatures below 40 °F (4 °C), consult Henry® Product Support: 800-486-1278.

40 °F (4 °C)→ add 10 volume oz. per gallon

50 °F (10 °C)→ add 8 volume oz. per gallon

60 °F (16 °C)→ add 6 volume oz. per gallon

70 °F (21 °C)→ add 4 volume oz. per gallon

80 °F (27 °C)→ add 3 volume oz. per gallon

90 °F (32 °C)→ add 2 volume oz. per gallon

Do not mix new material with old, uncured material as this can significantly reduce work times. Use new pails frequently.

**Pot life:** 10-15 minutes if **Pumadeq Catalyst** mix volumes followed. The working time of all **Pumadeq System** materials will be influenced by the amount of **Pumadeq Catalyst** added, the length of time they are mixed, how quickly they are removed from the mixing pail, and the substrate and ambient temperatures. Apply onto substrate and spread to prolong working time.

**Product application:** For best results, use small batch sizes (start with 1 gallon). After mixing thoroughly, apply onto surface, as soon as possible. **Pumadeq Flex 31MV** is applied evenly by medium nap (1/2") roller and brush.

Do not install **Pumadeq Flex 31MV** beyond cured primer.

Extend **Pumadeq Flex 31MV** one (1) inch (2.5 cm) beyond anticipated area of fabric reinforcement.

Roll or brush fabric for proper adhesion and removal of voids, folds, and wrinkles.

Lap adjoining fabric edges a minimum of three (3) inches (7.5 cm).

Ensure voids at edges of **Henry® Pumadeq Fleece** are filled with **Pumadeq Flex 31MV**.

**Application rate:** Install one (1) layer of **Pumadeq Flex 31MV** at 30 sq.ft./gal.

Back coat N-Fleece with **Pumadeq™ Flex 31MV** before applying on vertical surfaces.

Apply second layer of **Pumadeq Flex 31MV** at 50 sq.ft./gal.

Total rate for two coats = 20 sq.ft./gal.

Allow for saturation of rollers and brushes.

Rates will change depending on surface profile (>CSP 3-4).

**Thickness: Wet and dry film thickness ( WFT- DFT):** 80 mils

**Re-coat and traffic times:** Minimum 1 hour. If the surface is contaminated or overcoat times exceed 48 hours, clean with a clean cloth and **Henry® Pumadeq Cleaning Fluid**. Allow **Pumadeq Cleaning Fluid** to evaporate before over coating.

The new coating must be applied after 15 minutes minimum, 1 hour maximum of **Pumadeq Cleaning Fluid** application or it will have to be re-applied. MEK or Acetone can also be used, following the same procedures.

**Product restrictions and limitations:** If under catalyzed or mixing not thorough, the resin will not cure (remain sticky and smell). It must be completely removed by scrapping and wiping with **Pumadeq Cleaning Fluid**.

## Pumadeq™ Flex 31MV

---

**NOTE:** Before using **Pumadeq Flex 31MV**, please refer to Safety Data Sheet (SDS). Ensure the same safe working methods are followed for all persons in the work area. Wear suitable protective clothing, butyl rubber or nitrile gloves, and safety goggles with side shields during mixing and application.

When **Pumadeq Flex 31MV** is applied in enclosed areas without natural ventilation, forced ventilation must be arranged. Avoid strong concentration of vapor as well as direct contact with skin or eyes. If concentration exceeds recommended limits in SDS, a NIOSH approved respirator (OSHA 29 CFR 1910.134) is required. **Pumadeq Flex 31MV** has a low flashpoint; keep away from all sources of ignition and do not smoke. Uncured polymers, resins and catalyst powder may be toxic. They may cause allergic reactions or hypersensitivity reactions.  
Contact with skin – wash immediately with soap and water  
Contact with eyes – rinse immediately with lots of water and seek medical attention

### Coverage

---

Application rates should be adjusted to meet each project's specified requirements. Coverage rates are theoretical and do not take into account material loss due to project conditions and working methods.

- For Henry® System Warranty and Gold Seal Warranty requirements, refer to the appropriate approved Henry® specification for application and coverage rate requirements.

### Clean-up

---

Clean-up of tools and equipment may be accomplished by using **Pumadeq Cleaning Fluid**, Acetone, or MEK. Read and follow all Health and Safety instructions on SDS. Wash body with soap and water. Ensure all materials are mixed and cured before disposal, in accordance with federal, state, and local regulations. Dispose of all packaging in accordance with federal, state, and local regulations.

### Packaging

---

2.5 gallons, in metal pail  
5 gallons, in metal pail

### Colors

---

White  
Gray

### Shelf Life/ Storage

---

One year in unopened containers stored between 50 °F (10 °C) and 75° F (24 °C) under dry, ventilated conditions and out of direct sunlight. Storing the material at a higher temperature may reduce its shelf life. Keep in an upright position and do not over stack.

For more information, visit [www.henry.com](http://www.henry.com) or for technical assistance call us at 800-486-1278. For more information on Henry® product warranty and liability disclaimer please visit [www.henry.com/warranty](http://www.henry.com/warranty). Refer to the Safety Data Sheet prior to using this product. The Safety Data Sheet is available at [www.henry.com](http://www.henry.com) or by emailing Henry® Product Support at [productsupport@henry.com](mailto:productsupport@henry.com) or by calling 800-486-1278.

Henry is a registered trademark of Henry Company.

The technical and application information herein is based on the present state of our best scientific and practical knowledge. As the information herein is of a general nature, no assumption can be made as to a product's suitability for a particular use or application and no warranty as to its accuracy, reliability or completeness either expressed or implied is given other than those required by law. The user is responsible for checking the suitability of products for their intended use. Henry® Company data sheets are updated on a regular basis; it is the user's responsibility to obtain and to confirm the most recent version. Information contained in this data sheet may change without notice.



Physical property	Typical value	Test method
Appearance	Gray	
Solids Content by Volume	100%	ASTM D1644-2001, Method A
Elongation	88%	D412-06ae2 (as per C957M-10)
Hardness	58 Shore D	D2240-05 (as per C836M-10)
Tear Resistance	230 pli	D624-00 (2007)
Tensile Strength	1873 psi	D412-06ae2 (as per C957M-10)
VOC Content (maximum)	0 g/l	ASTM C1250-05

### Description

**Henry® GP Wearcoat** is a 100% solids, two-component, polyurethane coating, fully broadcast with aggregate, to form a flexible, hard wearing, anti-skid, traffic surface.

**GP Wearcoat** also forms a surface for strong adhesion by mortars, concrete, asphalt, adhesives and sealants.

### Features

- Flexible, hard wearing, anti-skid traffic surface
- Cures quickly at low temperatures
- Low odor, solvent free and VOC compliant

### Usage

**GP Wearcoat** is used as a hard-wearing traffic surface for:

- Parking Decks, Loading Docks, Balconies, Walkways
- Protected Membrane Roofing (PMR)
- Plaza Decks
- Inverted Roof Membrane Assemblies (IRMA)
- Green Roofs (VRA)
- Split Slabs
- Planters
- Terraces

### Application

**Site Conditions:** All surfaces should be prepared per the approved Henry specification and TechTalk.

Surface temperature must be at least 5° F above the dew point and rising.

Air and substrate temperatures must be between 40° F and 95° F. Relative humidity must be less than 80%.

**Surface Prep:** Surfaces to be over-coated must be clean, dry and free of contaminants that would impair adhesion.

If there are any doubts about suitability of a substrate, further advice should be sought from a Henry representative and a small trial area should be applied and tested appropriately.

**Product Mixing:** **GP Wearcoat** Parts A & B are pre-measured.

Mix all Part A with all of Part B.

They must be thoroughly mixed, using an electric, slow speed (300-400rpm), high torque drill with spiral (Jiffy) mixing paddle.

**Mix Ratio by Volume:**

1. Dispense Part A into a separate, clean, dry mixing pail. Mix for 30 seconds, taking care not to hit the sides.
2. Add Part B, taking care not to hit the sides, and mix for a minimum 1 minute.

Work the mixing paddle around the sides and bottom of the mixing pail to achieve a uniform, streak free, homogenous liquid. Scrape out all the material from the mixing pail.

## Henry GP Wearcoat

---

Decant to a new pail and use immediately

Do not mix new material with old, uncured material as this can significantly reduce work times. Use new pails frequently. Decant newly mixed material into smaller containers or onto substrate and spread to prolong working time

**Pot Life @ 68° F: 15 minutes.** The working time and viscosity of **GP Wearcoat** will be influenced by the length of time it is mixed (longer mixing results in shorter pot life), the substrate and ambient temperatures and how quickly it is removed from the mixing pail and spread on the substrate.

**Application: GP Wearcoat** is applied evenly by notched (3/16") squeegee and back rolled with a heavy-duty roller arm and medium nap (1/2") roller to assist leveling.

When **GP Wearcoat** becomes less fluid, back roll one more time to ensure it stays on substrate high points.

When **GP Wearcoat** has a sticky, "taffy" like consistency (usually 15-20 minutes @ 68° F), broadcast clean, dry aggregate as specified.

Apply aggregate by shovel or hopper gun, in multiple passes, allowing aggregate to "fall" vertically onto the **GP Wearcoat**

### Application Rate:

- Apply in one coat at a rate of 45-65 sf/gal (150-220 st/ 3.35 gal kit), depending on Henry specification
- Allow for saturation of rollers and brushes

**WFT-DFT:** Both 24-35 mils, depending on application rate.

### Re-coat and Traffic Times after application:

Minimum @ 68° F = 4 hours

Maximum 24 hours. No maximum time when fully broadcast with sand but must be cleaned thoroughly before over coating

Colder temperatures will increase this time.

### Product Restrictions and Limitations:

Can be rained on after 3 hrs. @68° F

Can be walked on after 4 hrs. @68° F

Colder temperatures will increase these times

**NOTE:** Before using **GP Wearcoat**, please refer to Safety Data Sheet (SDS). Ensure the same safe working methods are followed for all persons in the work area. Wear suitable protective clothing, butyl rubber or nitrile gloves and safety goggles with side shields during mixing and application.

Respiratory masks should be worn at all times when adequate ventilation does not exist.

A NIOSH/MSHA (TC-23C-1809), multi gas vapor respirator is acceptable.

Avoid strong concentration of vapor as well as direct contact with skin or eyes.

Uncured resins may be toxic. They may cause allergic reactions or hypersensitivity reactions

Contact with skin – wash immediately with soap and water.

Contact with eyes – rinse immediately with lots of water and seek medical attention.

## Coverage

---

Application rates should be adjusted to meet each project's specified requirements. Coverage rates are theoretical and do not take into account material loss due to project conditions and working methods.

- For Henry System Warranty and Gold Seal Warranty requirements, refer to appropriate approved Henry specification for application and coverage rate requirements.

## Clean-up

---

Clean-up of tools and equipment may be accomplished by using Acetone or MEK. Read and follow all Health and Safety instructions on SDS. Wash body with soap and water. Ensure all materials are mixed and cured before disposal, in accordance with federal, state, and local regulations. Dispose of all packaging in accordance with federal, state, and local regulations.

## Product contents / packaging size

---

Part A 3 gal / 3.5 gal container

Part B .35 gal / 1 gal container

---

**Henry® Company**, 999 N. Pacific Coast Highway, Ste. 800, El Segundo, CA 90245

**Tel:** 800-486-1278 **Email:** techservices@henry.com

www.henry.com

**Revision Date:** 11/5/2019

**Storage**

---

One year in unopened containers stored between 50° F and 80° F under dry, ventilated conditions, and out of direct sunlight. Storing the material at a higher temperature may reduce its shelf life. Keep in an upright position and do not over stack.

For more information, visit [www.henry.com](http://www.henry.com) or for technical assistance call us at 800-486-1278. For more information on the Henry® product warranty and liability disclaimer please visit [www.henry.com/warranty](http://www.henry.com/warranty). Refer to the Safety Data Sheet prior to using this product. The Safety Data Sheet is available at [www.henry.com](http://www.henry.com) or by emailing Henry® Product Support at [productsupport@henry.com](mailto:productsupport@henry.com) or by calling 800-486-1278.

Henry is a registered trademark of Henry Company.  
Covered by US patent 6,901,712; Canadian patent 2,413,550.

The technical and application information herein is based on the present state of our best scientific and practical knowledge. As the information herein is of a general nature, no assumption can be made as to a product's suitability for a particular use or application and no warranty as to its accuracy, reliability or completeness either expressed or implied is given other than those required by law. The user is responsible for checking the suitability of products for their intended use. Henry® Company data sheets are updated on a regular basis; it is the user's responsibility to obtain and to confirm the most recent version. Information contained in this data sheet may change without notice.

Physical property	Typical value	Test method
Appearance	Mid/Dark Gray, Custom Color	
Solids Content by Volume	100%	ASTM D1644-2001, Method A
Elongation	800%	D412-06ae2 (as per C957M-10)
Hardness	85 Shore A	D2240-05 (as per C836M-10)
Tear Resistance	353 pli	D624-00 (2007)
Tensile Strength	2500 psi	D412-06ae2 (as per C957M-10)
VOC Content (maximum)	0 g/l	ASTM C1250-05

### Description

Henry® GP Topcoat is a two-component aliphatic polyurea coating used as a colored topcoat. GP Topcoat is designed to form an elastic, strong, UV and color stable coating with excellent abrasion resistance.

### Features

- Elastic, hard wearing, abrasion resistant
- UV stable and color stable
- Low odor and VOC compliant
- Can be left exposed to ponded water
- Chemically resistant

### Usage

GP Topcoat is used as a flexible, UV and color stable topcoat for:

- Parking Decks, Loading Docks, Balconies, Walkways, Mechanical rooms
- Exposed membranes, where long-term color stability is required

### Application

**Site Conditions:** All surfaces should be prepared per the approved Henry specification. Surface temperature must be at least 5° F above the dew point and rising. Air and substrate temperatures must be between 40° F and 95° F.

**Surface Prep:** Surfaces to be over-coated must be clean, dry and free of contaminants that would impair adhesion. If there are any doubts about suitability of a substrate, further advice should be sought from a Henry representative and a small trial area should be applied and tested appropriately.

**Product Mixing:** GP Topcoat Parts A & B are pre-measured. Mix all Part A (resin) with all of Part B (hardener). They must be thoroughly mixed, using an electric, slow speed (300-400rpm), high torque drill with spiral (Jiffy) mixing paddle.

#### Mix Ratio by Volume:

1. Dispense Part A into a separate, clean, dry mixing pail. Mix for 30 seconds, taking care not to hit the sides.
2. Add Part B, taking care not to hit the sides, and mix for a minimum 1 minute.

Work the mixing paddle around the sides and bottom of the mixing pail to achieve a uniform, streak free, homogenous liquid. Do not mix in an up and down motion. Scrape out all the material from the mixing pail. Decant to a new pail and use immediately

Do not mix new material with old, uncured material as this can significantly reduce work times. Use new pails frequently. Decant newly mixed material into smaller containers or onto substrate and spread to prolong working time



## Henry GP Topcoat

---

**Pot Life @ 68 F: 15 minutes.** The working time and viscosity of **GP Topcoat** will be influenced by the length of time it is mixed (longer mixing results in shorter pot life), the substrate and ambient temperatures and how quickly it is removed from the mixing pail and spread on the substrate.

**Application: GP Topcoat** is applied evenly by flat squeegee, roller and brush  
After spreading by squeegee, use a heavy-duty roller arm applying moderate pressure to force **GP Topcoat** into aggregate voids  
The roller sleeve nap will depend on the size of anti-skid aggregate being covered, usually 3/8"

### Application Rate: Refer to Dundeq specification

- Pedestrian 5-year traffic system - applied in one coat @ 100sf/gallon (500/5-gal.kit)
- Pedestrian 10-year traffic system - applied in two coats @ 100sf/gallon (500sf/5-gal. kit) + 120sf/gallon (600sf/5gal. kit)
- Vehicular light duty areas - applied in one coat @ 80sf/gallon (400sf/5-gal.kit)
- Vehicular medium duty areas - applied in two coats @ 100sf/gallon (500sf/5-gal. kit) + 100sf/gallon (500sf/5gal. kit)
- Vehicular heavy duty areas (onto GP Wear Coat and aggregate) - applied in one coat @ 90sf/gallon (450/5-gal.kit)
- As a Topcoat over **FX 400** membrane, apply in two coat @ 150sf/gallon (750sf/5gal. kit) + 150sf/gallon (750sf/5gal. kit)  
Allow for saturation of rollers

**WFT-DFT:** 12-20 mils, depending on application type and surface profile

### Re-coat and Traffic Times after application:

Minimum @ 68° F = 6 hours, and tack-free before re-coating

Maximum 48 hours. If this time is exceeded, wipe with Acetone or MEK and a clean cloth.

Allow solvent to fully evaporate

12 hours before pedestrian traffic @ 68° F

24 hours before vehicular traffic @ 68° F

Colder temperatures will increase these times

### Product Restrictions and Limitations:

**NOTE:** Before using **GP Topcoat**, please refer to Safety Data Sheet (SDS). Ensure the same safe working methods are followed for all persons in the work area. Wear suitable protective clothing, butyl rubber or nitrile gloves and safety goggles with side shields during mixing and application.

Respiratory masks should be worn at all times when adequate ventilation does not exist.

A NIOSH/MSHA (TC-23C-1809), multi gas vapor respirator is acceptable.

Avoid strong concentration of vapor as well as direct contact with skin or eyes.

Uncured resins are corrosive, toxic or both. They may cause allergic reactions or hypersensitivity reactions.

Contact with skin – wash immediately with soap and water.

Contact with eyes – rinse immediately with lots of water and seek medical attention.

## Coverage

---

Application rates should be adjusted to meet each project's specified requirements.

Coverage rates are theoretical and do not take into account material loss due to project conditions and working methods.

- For Henry System Warranty and Gold Seal Warranty requirements, refer to appropriate approved Henry specification for application and coverage rate requirements.

## Clean-up

---

Clean-up of tools and equipment may be accomplished by using Acetone or MEK. Read and follow all Health and Safety instructions on SDS. Wash body with soap and water. Ensure all materials are mixed and cured before disposal, in accordance with federal, state, and local regulations. Dispose of all packaging in accordance with federal, state, and local regulations.

## Product size/packaging

---

Part A Resin 4.0 gal/ 5 gal container

Part B Hardener 1.0 gal/ 1 gal container

### Storage

---

One year in unopened containers stored between 60° F and 90° F under dry, ventilated conditions, and out of direct sunlight. Storing the material at a higher temperature may reduce its shelf life. Keep in an upright position and do not over stack.

For more information, visit [www.henry.com](http://www.henry.com) or for technical assistance call us at 800-486-1278. For more information on the Henry® product warranty and liability disclaimer please visit [www.henry.com/warranty](http://www.henry.com/warranty). Refer to the Safety Data Sheet prior to using this product. The Safety Data Sheet is available at [www.henry.com](http://www.henry.com) or by emailing Henry® Product Support at [productsupport@henry.com](mailto:productsupport@henry.com) or by calling 800-486-1278.

Henry is a registered trademark of Henry Company.  
Covered by US patent 6,901,712; Canadian patent 2,413,550.

The technical and application information herein is based on the present state of our best scientific and practical knowledge. As the information herein is of a general nature, no assumption can be made as to a product's suitability for a particular use or application and no warranty as to its accuracy, reliability or completeness either expressed or implied is given other than those required by law. The user is responsible for checking the suitability of products for their intended use. Henry® Company data sheets are updated on a regular basis; it is the user's responsibility to obtain and to confirm the most recent version. Information contained in this data sheet may change without notice.



Physical property	Typical value	Test method
Appearance	Clear	-

### Description

**Henry® FX Activator** is a water soluble, organic solvent stripping agent.

**FX Activator** increases the bond between existing FX membranes and other materials being applied onto them.

### Features

- Reactivates FX membranes
- Low odor
- High flash point

### Usage

**FX Activator** is used to “reactivate” FX membranes to ensure maximum bond of materials applied over them.

FX membranes must be reactivated after 24 hours of curing when applying FX membranes or materials over them.

**FX Activator** can also be used on other polyurethanes and epoxies.

### Application

**Site Conditions:** All surfaces should be prepared per the approved Henry specification.

**Surface Prep:** Substrates must be free of dirt and dust.

If there are any doubts about suitability of a substrate, further advice should be sought from a Henry representative and a small trial area should be applied and tested appropriately.

**Product Mixing:** **FX Activator** must be thoroughly stirred.

**Mix Ratio:** **FX Activator** is a single component product

**Pot Life @ 68° F:** Not Applicable. Ensure material in pail is thoroughly sealed.

**Product Application:** **FX Activator** is applied evenly by brush or spray.

Do not allow FX Activator to pond on the coating surface. Wipe puddles immediately with a clean cloth.

**Application Rate:**

- Apply in one, thin coat.

**WFT-DFT:** less than 1 mil.

**Re-coat and Traffic Times after application:**

Minimum @ 68° F = once FX Activator has completely flashed off or dissipated and the FX membrane surface is tacky.

Maximum = 1 hour

**Product Restrictions and Limitations:**

FX Activator must be re-applied if the FX membrane surface is not tacky or the maximum over-coat period of 1 hour is exceeded.

**NOTE:** Before using **FX Activator**, please refer to Safety Data Sheet (SDS). Ensure the same safe working methods are followed for all persons in the work area. Wear suitable protective clothing, butyl rubber or nitrile gloves and safety goggles with side shields during mixing and application.

Do not use near high heat or open flame.

Wear rubber or leather boots.

Respiratory masks should be worn at all times when adequate ventilation does not exist.

## Henry FX Activator

---

A NIOSH/MSHA (TC-23C-1809), multi gas vapor respirator is acceptable.  
Observe OSHA regulations for respirator use (29 CFR 1910.134).  
Avoid direct contact with skin or eyes.  
Uncured resin is corrosive, toxic or both. May cause allergic reactions or hypersensitivity reactions  
Contact with skin – wash immediately with soap and water.  
Contact with eyes – rinse immediately with lots of water and seek medical attention.

## Coverage

---

Application rates should be adjusted to meet each project's specified requirements. Coverage rates are theoretical and do not take into account material loss due to project conditions and working methods.

- For Henry System Warranty and Gold Seal Warranty requirements, refer to appropriate approved Henry specification for application and coverage rate requirements.

## Clean-up

---

Clean-up of tools and equipment may be accomplished by using Xylene or MEK. Read and follow all Health and Safety instructions on SDS. Wash body with soap and water. Ensure all materials are mixed and cured before disposal, in accordance with federal, state, and local regulations. Dispose of all packaging in accordance with federal, state, and local regulations.

## Product contents / packaging size

---

1 gal / 1 gal container

## Storage

---

Two years in original, unopened containers between 55° F and 90° F. Lower temperatures may cause crystallization.  
Storing the material at a higher temperature may reduce its shelf life.  
Under dry, ventilated conditions and out of direct sunlight. Keep in an upright position and do not over stack.

For more information, visit [www.henry.com](http://www.henry.com) or for technical assistance call us at 800-486-1278. For more information on the Henry® product warranty and liability disclaimer please visit [www.henry.com/warranty](http://www.henry.com/warranty). Refer to the Safety Data Sheet prior to using this product. The Safety Data Sheet is available at [www.henry.com](http://www.henry.com) or by emailing Henry® Product Support at [productsupport@henry.com](mailto:productsupport@henry.com) or by calling 800-486-1278.

Henry is a registered trademark of Henry Company.  
Covered by US patent 6,901,712; Canadian patent 2,413,550.

The technical and application information herein is based on the present state of our best scientific and practical knowledge. As the information herein is of a general nature, no assumption can be made as to a product's suitability for a particular use or application and no warranty as to its accuracy, reliability or completeness either expressed or implied is given other than those required by law. The user is responsible for checking the suitability of products for their intended use. Henry® Company data sheets are updated on a regular basis; it is the user's responsibility to obtain and to confirm the most recent version. Information contained in this data sheet may change without notice.



# SAFETY DATA SHEET

Issue Date 29-Sep-2019

Revision Date 29-Sep-2019

Version 1

## 1. IDENTIFICATION

### Product identifier

**Product Name** PRODEQ FX400 ISO PART A

### Other means of identification

**Product Code** TQ909

**Synonyms** None

### Recommended use of the chemical and restrictions on use

**Recommended Use** Industrial Coatings

**Uses advised against** No information available

### Details of the supplier of the safety data sheet

#### **Supplier Address**

HENRY COMPANY  
15 Wallsend Dr.  
Scarborough, ON M1E 3X6  
Canada  
Web Site: [www.henry.com](http://www.henry.com)  
[www.ca.henry.com](http://www.ca.henry.com)

#### **Manufacturer Address**

HENRY COMPANY  
999 N. Pacific Coast Hwy., Suite 800  
El Segundo, CA 90245-2716  
Web Site: [www.henry.com](http://www.henry.com) [www.ca.henry.com](http://www.ca.henry.com)

### Emergency telephone number

#### **Company Phone Number**

800-486-1278

#### **Emergency Telephone**

US and Canada only (toll-free) : 3E Company - 1-866-519-4752 (access code 334832)  
US/Canada, all other countries: 3E Company - +1-760-476-3962 (access code 334832)  
Mexico (additional contact option): 3E Company - +52 55 41696225 (Code 334832)

## 2. HAZARDS IDENTIFICATION

### Classification

#### **OSHA Regulatory Status**

This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200) and Canadian Workplace Hazardous Material Information System (WHMIS)

Acute toxicity - Inhalation (Dusts/Mists)	Category 4
Skin corrosion/irritation	Category 2
Serious eye damage/eye irritation	Category 2
Respiratory sensitization	Category 1
Skin sensitization	Category 1
Specific target organ toxicity (single exposure)	Category 3
Specific target organ toxicity (repeated exposure)	Category 2

### Label elements

#### Emergency Overview

Danger

**Hazard statements**

Harmful if inhaled  
Causes skin irritation  
Causes serious eye irritation  
May cause allergy or asthma symptoms or breathing difficulties if inhaled  
May cause an allergic skin reaction  
May cause respiratory irritation  
May cause damage to organs through prolonged or repeated exposure

**Appearance** viscous**Physical state** liquid**Odor** Aromatic**Precautionary Statements - Prevention**

Obtain special instructions before use  
Do not handle until all safety precautions have been read and understood  
Use personal protective equipment as required  
Use only outdoors or in a well-ventilated area  
Wash face, hands and any exposed skin thoroughly after handling  
In case of inadequate ventilation wear respiratory protection  
Contaminated work clothing should not be allowed out of the workplace  
Wear protective gloves  
Do not breathe dust/fume/gas/mist/vapors/spray

**Precautionary Statements - Response**

IF exposed or concerned: Get medical advice/attention  
IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing  
If eye irritation persists: Get medical advice/attention  
IF ON SKIN: Wash with plenty of soap and water  
Take off contaminated clothing and wash before reuse  
If skin irritation or rash occurs: Get medical advice/attention  
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing  
If experiencing respiratory symptoms: Call a POISON CENTER or doctor/physician

**Precautionary Statements - Storage**

Store locked up  
Store in a well-ventilated place. Keep container tightly closed

**Precautionary Statements - Disposal**

Dispose of contents/container to an approved waste disposal plant

**Hazards not otherwise classified (HNOC)**

Not applicable

**Other Information**

Not applicable.

**Unknown acute toxicity**

0% of the mixture consists of ingredient(s) of unknown toxicity

**3. COMPOSITION/INFORMATION ON INGREDIENTS****Substance**

Chemical Name	CAS No	Weight-%
Poly[oxy(methyl-1,2-ethanedyl)], .alpha.-hydro.-omega.-hydroxy-, polymer with 1,1-methylenebis[isocyanatobenzene] *	39420-98-9	30 - 60
Benzene, 1,1-methylenebis[isocyanato- *	26447-40-5	10 - 30
4,4-Methylenediphenyl diisocyanate *	101-68-8	10 - 30
Propylene carbonate *	108-32-7	5 - 10
Benzene, 1,1-methylenebis[isocyanato-, homopolymer *	39310-05-9	3 - 7

\*The exact percentage (concentration) of composition has been withheld as a trade secret.

#### 4. FIRST AID MEASURES

##### Description of first aid measures

<b>General advice</b>	In case of accident or unwellness, seek medical advice immediately (show directions for use or safety data sheet if possible). If symptoms persist, call a physician.
<b>Eye contact</b>	Call a physician immediately. Immediately flush with plenty of water. After initial flushing, remove any contact lenses and continue flushing for at least 15 minutes. If symptoms persist, call a physician.
<b>Skin contact</b>	Wash contaminated clothing before reuse. Wash off immediately with plenty of water. If symptoms persist, call a physician.
<b>Inhalation</b>	Immediate medical attention is required. Move victim to fresh air. Administer oxygen if breathing is difficult. If breathing is irregular or stopped, administer artificial respiration.
<b>Ingestion</b>	Call a physician or poison control center immediately. Do NOT induce vomiting. Drink plenty of water. Never give anything by mouth to an unconscious person.
<b>Self-protection of the first aider</b>	Ensure that medical personnel are aware of the material(s) involved and take precautions to protect themselves.

##### Most important symptoms and effects, both acute and delayed

<b>Symptoms</b>	May cause allergy or asthma symptoms or breathing difficulties if inhaled. May cause allergic skin reaction.
-----------------	--

##### Indication of any immediate medical attention and special treatment needed

<b>Note to physicians</b>	May cause sensitization in susceptible persons. Treat symptomatically.
---------------------------	--

#### 5. FIRE-FIGHTING MEASURES

##### Suitable extinguishing media

Use extinguishing measures that are appropriate to local circumstances and the surrounding environment.

**Unsuitable extinguishing media** CAUTION: Use of water spray when fighting fire may be inefficient.

##### Specific hazards arising from the chemical

Thermal decomposition can lead to release of irritating and toxic gases and vapors.

##### Explosion data

**Sensitivity to Mechanical Impact** None.

**Sensitivity to Static Discharge** None.

##### Protective equipment and precautions for firefighters

As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

#### 6. ACCIDENTAL RELEASE MEASURES

**Personal precautions, protective equipment and emergency procedures**

**Personal precautions** Evacuate personnel to safe areas. Do not touch or walk through spilled material. Use personal protective equipment as required.

**Environmental precautions**

**Environmental precautions** Prevent further leakage or spillage if safe to do so. Prevent product from entering drains. Do not flush into surface water or sanitary sewer system.

**Methods and material for containment and cleaning up**

**Methods for containment** If possible, turn leaking containers so that gas escapes rather than liquid. Absorb spill with inert material (e.g. dry sand or earth), then place in a chemical waste container. Transport to well ventilated area and treat with neutralizing solution: mixture of 80% water and 20% non-ionic surfactant Tergitol TMN-10; or 90% water, 3-8% concentrated ammonia and 2% detergent. Add about 10 parts of neutralizer per part of isocyanate, with mixing. Allow substance to evaporate.

**Methods for cleaning up** Do not direct water at spill or source of leak. Decontaminate floor with decontamination solution letting stand for at least 15 minutes.

## 7. HANDLING AND STORAGE

**Precautions for safe handling**

**Advice on safe handling** Avoid contact with skin, eyes or clothing. Ensure adequate ventilation, especially in confined areas. Avoid breathing vapors or mists.

**Conditions for safe storage, including any incompatibilities**

**Storage Conditions** Keep containers tightly closed in a cool, well-ventilated place.

**Incompatible materials** Water. Alcohols. Strong bases. Strong oxidizing agents. Finely powdered metals.

## 8. EXPOSURE CONTROLS/PERSONAL PROTECTION

**Control parameters****Exposure Guidelines**

Chemical Name	ACGIH TLV	OSHA PEL	NIOSH IDLH
Benzene, 1,1-methylenebis[isocyanato- 26447-40-5	-	Ceiling: 0.02 ppm Ceiling: 0.2 mg/m <sup>3</sup>	-
4,4-Methylenediphenyl diisocyanate 101-68-8	TWA: 0.005 ppm	Ceiling: 0.02 ppm Ceiling: 0.2 mg/m <sup>3</sup>	IDLH: 75 mg/m <sup>3</sup> Ceiling: 0.020 ppm 10 min Ceiling: 0.2 mg/m <sup>3</sup> 10 min TWA: 0.005 ppm TWA: 0.05 mg/m <sup>3</sup>

*NIOSH IDLH Immediately Dangerous to Life or Health*

**Appropriate engineering controls**

**Engineering Controls** Showers  
Eyewash stations  
Ventilation systems.

**Individual protection measures, such as personal protective equipment**

**Eye/face protection** Wear safety glasses with side shields (or goggles).

**Skin and body protection** Wear protective gloves and protective clothing.



**Respiratory protection**

If exposure limits are exceeded or irritation is experienced, NIOSH/MSHA approved respiratory protection should be worn. Positive-pressure supplied air respirators may be required for high airborne contaminant concentrations. Respiratory protection must be provided in accordance with current local regulations.

**General Hygiene Considerations**

Handle in accordance with good industrial hygiene and safety practice.

## 9. PHYSICAL AND CHEMICAL PROPERTIES

**Information on basic physical and chemical properties**

<b>Physical state</b>	liquid	<b>Odor</b>	Aromatic
<b>Appearance</b>	viscous	<b>Odor threshold</b>	No information available
<b>Color</b>	brown		

<u>Property</u>	<u>Values</u>	<u>Remarks • Method</u>
<b>pH</b>	No information available	
<b>Melting point / freezing point</b>	No information available	
<b>Boiling point / boiling range</b>	No information available	
<b>Flash point</b>	198 °C / 388.4 °F	
<b>Evaporation rate</b>	No information available	
<b>Flammability (solid, gas)</b>	No information available	
<b>Flammability Limit in Air</b>		
<b>Upper flammability limit:</b>	No information available	
<b>Lower flammability limit:</b>	No information available	
<b>Vapor pressure</b>	~0	
<b>Vapor density</b>	No information available	
<b>Relative density</b>	1.234	
<b>Water solubility</b>	insoluble Reacts with water	
<b>Solubility in other solvents</b>	No information available	
<b>Partition coefficient</b>	No information available	
<b>Autoignition temperature</b>	No information available	
<b>Decomposition temperature</b>	No information available	
<b>Kinematic viscosity</b>	No information available	
<b>Dynamic viscosity</b>	150-250 mPa s	
<b>Explosive properties</b>	No information available	
<b>Oxidizing properties</b>	No information available	

**Other Information**

<b>Softening point</b>	No information available
<b>Molecular weight</b>	No information available
<b>VOC Content (%)</b>	No information available
<b>Density</b>	No information available
<b>Bulk density</b>	No information available

## 10. STABILITY AND REACTIVITY

**Reactivity**

No data available

**Chemical stability**

Stable under recommended storage conditions.

**Possibility of Hazardous Reactions**

None under normal processing.

**Hazardous polymerization**      Hazardous polymerization may occur.

**Conditions to avoid**

Keep from any possible contact with water. Extremes of temperature and direct sunlight. Storage near to reactive materials.

**Incompatible materials**

Water. Alcohols. Strong bases. Strong oxidizing agents. Finely powdered metals.

**Hazardous Decomposition Products**

Carbon monoxide. Carbon dioxide (CO<sub>2</sub>). Nitrogen oxides (NO<sub>x</sub>). Hydrogen cyanide. Thermal decomposition can lead to release of irritating and toxic gases and vapors.

## 11. TOXICOLOGICAL INFORMATION

**Information on likely routes of exposure****Product Information**

<b>Inhalation</b>	May cause irritation of respiratory tract. May cause sensitization by inhalation. Harmful by inhalation.
<b>Eye contact</b>	Irritating to eyes.
<b>Skin contact</b>	Repeated or prolonged skin contact may cause allergic reactions with susceptible persons. Irritating to skin.
<b>Ingestion</b>	Based on available data, the classification criteria are not met.

Chemical Name	Oral LD50	Dermal LD50	Inhalation LC50
Benzene, 1,1-methylenebis[isocyanato- 26447-40-5	> 10000 mg/kg ( Rat )	> 10000 mg/kg ( Rabbit )	= 490 mg/m <sup>3</sup> ( Rat ) 4 h
4,4-Methylenediphenyl diisocyanate 101-68-8	= 31600 mg/kg ( Rat ) = 9200 mg/kg ( Rat )	-	= 369 mg/m <sup>3</sup> ( Rat ) 4 h
Propylene carbonate 108-32-7	= 29000 mg/kg ( Rat )	> 3000 mg/kg ( Rabbit )	-

**Information on toxicological effects**

**Symptoms** May cause an allergic skin reaction. Redness.

**Delayed and immediate effects as well as chronic effects from short and long-term exposure**

**Sensitization** May cause sensitization by inhalation. May cause sensitization by skin contact.  
**Germ cell mutagenicity** Based on available data, the classification criteria are not met.  
**Carcinogenicity** Based on available data, the classification criteria are not met.

Chemical Name	ACGIH	IARC	NTP	OSHA
Benzene, 1,1-methylenebis[isocyanato - 26447-40-5	-	Group 3	-	-
4,4-Methylenediphenyl diisocyanate 101-68-8	-	Group 3	-	-

*IARC (International Agency for Research on Cancer)  
 Group 3 - Not Classifiable as to Carcinogenicity in Humans  
 Not classifiable as a human carcinogen*

**Reproductive toxicity** Based on available data, the classification criteria are not met.  
**STOT - single exposure** May cause disorder and damage to the. Respiratory system. Eyes. Skin.  
**STOT - repeated exposure** Causes damage to organs through prolonged or repeated exposure.  
**Chronic toxicity** Repeated or prolonged exposure may cause central nervous system damage. Repeated or prolonged contact causes sensitization, asthma and eczemas.  
**Target Organ Effects** Respiratory system, Eyes, Skin, Central nervous system.  
**Aspiration hazard** Based on available data, the classification criteria are not met.

**Numerical measures of toxicity - Product Information**

The following values are calculated based on chapter 3.1 of the GHS document .

**ATEmix (oral)** 18,281.00 mg/kg  
**ATEmix (dermal)** 17,108.00 mg/kg  
**ATEmix (inhalation-dust/mist)** 3.30 mg/l

## 12. ECOLOGICAL INFORMATION

### Ecotoxicity

100 % of the mixture consists of component(s) of unknown hazards to the aquatic environment

Chemical Name	Algae/aquatic plants	Fish	Crustacea
Benzene, 1,1-methylenbis[isocyanato- 26447-40-5	3230: 96 h Skeletonema costatum mg/L EC50	-	1000: 24 h Daphnia magna mg/L EC50
Propylene carbonate 108-32-7	500: 72 h Desmodesmus subspicatus mg/L EC50	1000: 96 h Cyprinus carpio mg/L LC50 semi-static 5300: 96 h Leuciscus idus mg/L LC50 static	500: 48 h Daphnia magna mg/L EC50

### Persistence and degradability

No information available.

### Bioaccumulation

No information available.

Chemical Name	Partition coefficient
Benzene, 1,1-methylenbis[isocyanato- 26447-40-5	4.5
Propylene carbonate 108-32-7	0.48

### Other adverse effects

No information available

## 13. DISPOSAL CONSIDERATIONS

### Waste treatment methods

#### **Disposal of wastes**

Disposal should be in accordance with applicable regional, national and local laws and regulations.

#### **Contaminated packaging**

Do not reuse container.

## 14. TRANSPORT INFORMATION

DOT Not regulated

TDG Not regulated

IATA Not regulated

IMDG Not regulated

## 15. REGULATORY INFORMATION

### International Inventories

TSCA	Complies
DSL/NDSL	Complies
EINECS/ELINCS	Complies
IECSC	Complies
KECL	Complies
PICCS	Complies
AICS	Complies

### Legend:

TSCA - United States Toxic Substances Control Act Section 8(b) Inventory

DSL/NDSL - Canadian Domestic Substances List/Non-Domestic Substances List

EINECS/ELINCS - European Inventory of Existing Chemical Substances/European List of Notified Chemical Substances

ENCS - Japan Existing and New Chemical Substances  
 IECSC - China Inventory of Existing Chemical Substances  
 KECL - Korean Existing and Evaluated Chemical Substances  
 PICCS - Philippines Inventory of Chemicals and Chemical Substances  
 AICS - Australian Inventory of Chemical Substances

**US Federal Regulations**

**SARA 313**

Section 313 of Title III of the Superfund Amendments and Reauthorization Act of 1986 (SARA). This product contains a chemical or chemicals which are subject to the reporting requirements of the Act and Title 40 of the Code of Federal Regulations, Part 372

Chemical Name	SARA 313 - Threshold Values %
Benzene, 1,1-methylenebis[isocyanato- - 26447-40-5	1.0
4,4-Methylenediphenyl diisocyanate - 101-68-8	1.0

**SARA 311/312 Hazard Categories**

Acute health hazard	Yes
Chronic Health Hazard	Yes
Fire hazard	No
Sudden release of pressure hazard	No
Reactive Hazard	No

**CWA (Clean Water Act)**

This product does not contain any substances regulated as pollutants pursuant to the Clean Water Act (40 CFR 122.21 and 40 CFR 122.42)

**CERCLA**

This material, as supplied, contains one or more substances regulated as a hazardous substance under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302)

Chemical Name	Hazardous Substances RQs	CERCLA/SARA RQ	Reportable Quantity (RQ)
4,4-Methylenediphenyl diisocyanate 101-68-8	5000 lb	-	RQ 5000 lb final RQ RQ 2270 kg final RQ

**US State Regulations**

**California Proposition 65**

This product does not contain any Proposition 65 chemicals

**U.S. State Right-to-Know Regulations**

Chemical Name	New Jersey	Massachusetts	Pennsylvania
Benzene, 1,1-methylenebis[isocyanato- 26447-40-5	X	-	-
4,4-Methylenediphenyl diisocyanate 101-68-8	X	X	X

**U.S. EPA Label Information**

EPA Pesticide Registration Number Not applicable

**16. OTHER INFORMATION, INCLUDING DATE OF PREPARATION OF THE LAST REVISION**

<b>NFPA</b>	Health hazards 3	Flammability 1	Instability 0	Physical and Chemical Properties -
<b>HMIS</b>	Health hazards 3*	Flammability 1	Physical hazards 0	Personal protection X

Issue Date 29-Sep-2019

Revision Date 29-Sep-2019

Revision Note

No information available

**Disclaimer**

The information provided in this Material Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The

information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text.

**End of Safety Data Sheet**



# SAFETY DATA SHEET

Issue Date 29-Sep-2019

Revision Date 29-Sep-2019

Version 1

## 1. IDENTIFICATION

### Product identifier

**Product Name** PRODEQ FX400 GREEN PART B

### Other means of identification

**Product Code** TQ904GR

**UN/ID no** UN3066

**Synonyms** None

### Recommended use of the chemical and restrictions on use

**Recommended Use** Industrial Coatings

**Uses advised against** No information available

### Details of the supplier of the safety data sheet

#### **Supplier Address**

HENRY COMPANY  
15 Wallsend Dr.  
Scarborough, ON M1E 3X6  
Canada  
Web Site: [www.henry.com](http://www.henry.com)  
[www.ca.henry.com](http://www.ca.henry.com)

#### **Manufacturer Address**

HENRY COMPANY  
999 N. Pacific Coast Hwy., Suite 800  
El Segundo, CA 90245-2716  
Web Site: [www.henry.com](http://www.henry.com) [www.ca.henry.com](http://www.ca.henry.com)

### Emergency telephone number

**Company Phone Number** 800-486-1278

**Emergency Telephone** US and Canada only (toll-free) : 3E Company - 1-866-519-4752 (access code 334832)  
US/Canada, all other countries: 3E Company - +1-760-476-3962 (access code 334832)  
Mexico (additional contact option): 3E Company - +52 55 41696225 (Code 334832)

## 2. HAZARDS IDENTIFICATION

### Classification

#### **OSHA Regulatory Status**

This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Acute toxicity - Oral	Category 4
Skin corrosion/irritation	Category 1 Sub-category C
Serious eye damage/eye irritation	Category 1
Skin sensitization	Category 1
Specific target organ toxicity (single exposure)	Category 3
Specific target organ toxicity (repeated exposure)	Category 2

### Label elements

#### **Emergency Overview**

**Danger**

**Hazard statements**

Harmful if swallowed  
Causes severe skin burns and eye damage  
May cause an allergic skin reaction  
May cause respiratory irritation. May cause drowsiness or dizziness  
May cause damage to organs through prolonged or repeated exposure



**Appearance** viscous

**Physical state** liquid

**Odor** Slight Amine

#### **Precautionary Statements - Prevention**

Wash face, hands and any exposed skin thoroughly after handling  
Do not eat, drink or smoke when using this product  
Do not breathe dust/fume/gas/mist/vapors/spray  
Wear protective gloves/protective clothing/eye protection/face protection  
Contaminated work clothing should not be allowed out of the workplace  
Use only outdoors or in a well-ventilated area

#### **Precautionary Statements - Response**

IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing  
Immediately call a POISON CENTER or doctor/physician  
IF ON SKIN (or hair): Remove/Take off immediately all contaminated clothing. Rinse skin with water/shower  
If skin irritation or rash occurs: Get medical advice/attention  
Wash contaminated clothing before reuse  
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing  
Call a POISON CENTER or doctor/physician if you feel unwell  
IF SWALLOWED: Call a POISON CENTER or doctor/physician if you feel unwell  
Rinse mouth  
Do NOT induce vomiting

#### **Precautionary Statements - Storage**

Store locked up  
Store in a well-ventilated place. Keep container tightly closed

#### **Precautionary Statements - Disposal**

Dispose of contents/container to an approved waste disposal plant

#### **Hazards not otherwise classified (HNOC)**

Not applicable

#### **Other Information**

Toxic to aquatic life with long lasting effects. Toxic to aquatic life.

#### **Unknown acute toxicity**

0% of the mixture consists of ingredient(s) of unknown toxicity

### **3. COMPOSITION/INFORMATION ON INGREDIENTS**

#### **Substance**

Not applicable

#### **Mixture**

Chemical Name	CAS No	Weight-%
Polypropylene glycol *	25322-69-4	40 - 70
Diethyltoluenediamine *	68479-98-1	15 - 40
Propylene glycol diamine, 2-amino-, diether with Propylene *	9046-10-0	7 - 13

\*The exact percentage (concentration) of composition has been withheld as a trade secret.

#### 4. FIRST AID MEASURES

##### Description of first aid measures

<b>General advice</b>	Immediate medical attention is required.
<b>Eye contact</b>	Immediately flush with plenty of water. After initial flushing, remove any contact lenses and continue flushing for at least 15 minutes. Keep eye wide open while rinsing. Call a physician immediately.
<b>Skin contact</b>	Immediate medical attention is required. Wash off immediately with soap and plenty of water while removing all contaminated clothes and shoes.
<b>Inhalation</b>	Immediate medical attention is required. Remove to fresh air. If not breathing, give artificial respiration. Avoid direct contact with skin. Use barrier to give mouth-to-mouth resuscitation.
<b>Ingestion</b>	Do NOT induce vomiting. Call a physician or poison control center immediately. Never give anything by mouth to an unconscious person. Drink plenty of water.
<b>Self-protection of the first aider</b>	Use personal protective equipment as required. Avoid contact with skin, eyes or clothing.

##### Most important symptoms and effects, both acute and delayed

<b>Symptoms</b>	May cause redness and tearing of the eyes. Coughing and/ or wheezing. May cause skin irritation. May cause allergic skin reaction.
-----------------	--

##### Indication of any immediate medical attention and special treatment needed

<b>Note to physicians</b>	Treat symptomatically.
---------------------------	------------------------

#### 5. FIRE-FIGHTING MEASURES

##### Suitable extinguishing media

Use extinguishing measures that are appropriate to local circumstances and the surrounding environment. Dry chemical, CO<sub>2</sub>, sand, earth, water spray or regular foam.

**Unsuitable extinguishing media** Do not use a solid water stream as it may scatter and spread fire.

##### Specific hazards arising from the chemical

Thermal decomposition can lead to release of irritating and toxic gases and vapors.

##### Explosion data

**Sensitivity to Mechanical Impact** None.

**Sensitivity to Static Discharge** None.

##### Protective equipment and precautions for firefighters

As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

#### 6. ACCIDENTAL RELEASE MEASURES

##### Personal precautions, protective equipment and emergency procedures

<b>Personal precautions</b>	Use personal protective equipment as required. Keep people away from and upwind of spill/leak.
-----------------------------	--



**Environmental precautions**

**Environmental precautions** Prevent further leakage or spillage if safe to do so. Prevent product from entering drains.

**Methods and material for containment and cleaning up**

**Methods for containment** Prevent further leakage or spillage if safe to do so. Cover powder spill with plastic sheet or tarp to minimize spreading. Dike far ahead of liquid spill for later disposal.

**Methods for cleaning up** Cover liquid spill with sand, earth or other non-combustible absorbent material. Use personal protective equipment as required. Dam up. Take up mechanically, placing in appropriate containers for disposal. Clean contaminated surface thoroughly.

## 7. HANDLING AND STORAGE

**Precautions for safe handling**

**Advice on safe handling** Avoid contact with skin, eyes or clothing. Wash contaminated clothing before reuse. Use personal protective equipment as required. Do not breathe dust/fume/gas/mist/vapors/spray. Do not eat, drink or smoke when using this product.

**Conditions for safe storage, including any incompatibilities**

**Storage Conditions** Keep container tightly closed in a dry and well-ventilated place. Keep out of the reach of children.

**Incompatible materials** Strong oxidizing agents. Strong acids. Strong bases.

## 8. EXPOSURE CONTROLS/PERSONAL PROTECTION

**Control parameters**

**Exposure Guidelines** This product, as supplied, does not contain any hazardous materials with occupational exposure limits established by the region specific regulatory bodies.

**Appropriate engineering controls**

**Engineering Controls** Showers  
Eyewash stations  
Ventilation systems.

**Individual protection measures, such as personal protective equipment**

**Eye/face protection** Tight sealing safety goggles.

**Skin and body protection** Wear protective gloves and protective clothing.

**Respiratory protection** If exposure limits are exceeded or irritation is experienced, NIOSH/MSHA approved respiratory protection should be worn. Positive-pressure supplied air respirators may be required for high airborne contaminant concentrations. Respiratory protection must be provided in accordance with current local regulations.

**General Hygiene Considerations** When using do not eat, drink or smoke. Regular cleaning of equipment, work area and clothing is recommended. Avoid contact with skin, eyes or clothing. Wash hands thoroughly after handling. Keep away from food, drink and animal feeding stuffs.

## 9. PHYSICAL AND CHEMICAL PROPERTIES

**Information on basic physical and chemical properties**

**Physical state** liquid

<b>Appearance</b>	viscous	<b>Odor</b>	Slight Amine
<b>Color</b>	pigmented	<b>Odor threshold</b>	No information available
<b>Property</b>	<b>Values</b>	<b>Remarks • Method</b>	
<b>pH</b>	>10	solution (1 %)	
<b>Melting point / freezing point</b>	No information available		
<b>Boiling point / boiling range</b>	No information available		
<b>Flash point</b>	> 120 °C / 248 °F	Tag Closed Cup	
<b>Evaporation rate</b>	No information available		
<b>Flammability (solid, gas)</b>	No information available		
<b>Flammability Limit in Air</b>			
<b>Upper flammability limit:</b>	No information available		
<b>Lower flammability limit:</b>	No information available		
<b>Vapor pressure</b>	No information available		
<b>Vapor density</b>	>1		
<b>Relative density</b>	0.94		
<b>Water solubility</b>	negligible		
<b>Solubility in other solvents</b>	No information available		
<b>Partition coefficient</b>	No information available		
<b>Autoignition temperature</b>	No information available		
<b>Decomposition temperature</b>	No information available		
<b>Kinematic viscosity</b>	> 100 mm <sup>2</sup> /s	@ 40 °C	
<b>Dynamic viscosity</b>	No information available		
<b>Explosive properties</b>	Not an explosive		
<b>Oxidizing properties</b>	Not applicable		
<b><u>Other Information</u></b>			
<b>Softening point</b>	No information available		
<b>Molecular weight</b>	No information available		
<b>VOC Content (%)</b>	No information available		
<b>Density</b>	No information available		
<b>Bulk density</b>	No information available		

## 10. STABILITY AND REACTIVITY

### Reactivity

No data available

### Chemical stability

Stable under recommended storage conditions.

### Possibility of Hazardous Reactions

None under normal processing.

### Conditions to avoid

Elevated Temperature. Incompatible materials.

### Incompatible materials

Strong oxidizing agents. Strong acids. Strong bases.

### Hazardous Decomposition Products

Thermal decomposition can lead to release of irritating and toxic gases and vapors.

## 11. TOXICOLOGICAL INFORMATION

### Information on likely routes of exposure

#### Product Information

<b>Inhalation</b>	Irritating to respiratory system.
<b>Eye contact</b>	Corrosive to the eyes and may cause severe damage including blindness.
<b>Skin contact</b>	May cause burns. May cause sensitization by skin contact. Harmful in contact with skin.

**Ingestion**

Harmful if swallowed.

Chemical Name	Oral LD50	Dermal LD50	Inhalation LC50
Polypropylene glycol 25322-69-4	= 3750 mg/kg ( Rat ) > 2 g/kg ( Rat )	-	-
Diethyltoluenediamine 68479-98-1	= 472 mg/kg ( Rat ) = 485 mg/kg ( Rat )	= 700 mg/kg ( Rabbit )	-
Propylene glycol diamine, 2-amino-, diether with Propylene 9046-10-0	= 242 mg/kg ( Rat )	= 360 mg/kg ( Rabbit )	-

**Information on toxicological effects****Symptoms**

May cause an allergic skin reaction. Causes skin burns. May cause redness and tearing of the eyes. Coughing and/ or wheezing.

**Delayed and immediate effects as well as chronic effects from short and long-term exposure****Corrosivity**

Risk of serious damage to eyes. Causes burns.

**Sensitization**

May cause sensitization by skin contact.

**Germ cell mutagenicity**

Based on available data, the classification criteria are not met.

**Carcinogenicity**

Based on available data, the classification criteria are not met.

**Reproductive toxicity**

Based on available data, the classification criteria are not met.

**STOT - single exposure**

Target Organs. Respiratory system. Eyes. Skin.

**STOT - repeated exposure**

Causes damage to organs through prolonged or repeated exposure.

**Chronic toxicity**

May cause adverse effects on the bone marrow and blood-forming system. May cause adverse liver effects.

**Target Organ Effects**

blood, Central nervous system, Eyes, kidney, liver, Respiratory system, Skin, Urinary Tract.

**Aspiration hazard**

Based on available data, the classification criteria are not met.

**Numerical measures of toxicity - Product Information**

The following values are calculated based on chapter 3.1 of the GHS document .

ATEmix (oral) 324.00 mg/kg

ATEmix (dermal) 490.00 mg/kg

**12. ECOLOGICAL INFORMATION****Ecotoxicity**

Toxic to aquatic life with long lasting effects

0 % of the mixture consists of component(s) of unknown hazards to the aquatic environment

**Persistence and degradability**

No information available.

**Bioaccumulation**

No information available.

**Other adverse effects**

No information available

**13. DISPOSAL CONSIDERATIONS****Waste treatment methods****Disposal of wastes**

Disposal should be in accordance with applicable regional, national and local laws and regulations.

**Contaminated packaging**

Do not reuse container.

**US EPA Waste Number**

D002

## 14. TRANSPORT INFORMATION

**DOT**

UN/ID no	UN3066
Proper shipping name	Paint
Hazard Class	8
Packing Group	III
Special Provisions	B52, IB3, T4, TP1, TP29
Description	UN3066, Paint, 8, III
Emergency Response Guide Number	153

**TDG**

UN/ID no	UN3066
Proper shipping name	Paint
Hazard Class	8
Packing Group	III
Description	UN3066, Paint, 8, III

**IATA**

UN/ID no	UN3066
Proper shipping name	Paint
Hazard Class	8
Packing Group	III
ERG Code	8L
Special Provisions	A3, A72, A803, A192
Description	UN3066, Paint, 8, III

**IMDG**

UN/ID no	UN3066
Proper shipping name	Paint
Hazard Class	8
Packing Group	III
EmS-No	F-A, S-B
Special Provisions	163, 223
Description	UN3066, Paint, 8, III

## 15. REGULATORY INFORMATION

**International Inventories**

TSCA	Complies
DSL/NDSL	Complies
EINECS/ELINCS	Complies
IECSC	Complies
KECL	Complies
PICCS	Complies
AICS	Complies

**Legend:**

TSCA - United States Toxic Substances Control Act Section 8(b) Inventory  
 DSL/NDSL - Canadian Domestic Substances List/Non-Domestic Substances List  
 EINECS/ELINCS - European Inventory of Existing Chemical Substances/European List of Notified Chemical Substances  
 ENCS - Japan Existing and New Chemical Substances  
 IECSC - China Inventory of Existing Chemical Substances  
 KECL - Korean Existing and Evaluated Chemical Substances  
 PICCS - Philippines Inventory of Chemicals and Chemical Substances  
 AICS - Australian Inventory of Chemical Substances

**US Federal Regulations**

**SARA 313**

Section 313 of Title III of the Superfund Amendments and Reauthorization Act of 1986 (SARA). This product does not contain any chemicals which are subject to the reporting requirements of the Act and Title 40 of the Code of Federal Regulations, Part 372

**SARA 311/312 Hazard Categories**

<b>Acute health hazard</b>	Yes
<b>Chronic Health Hazard</b>	Yes
<b>Fire hazard</b>	No
<b>Sudden release of pressure hazard</b>	No
<b>Reactive Hazard</b>	No

**CWA (Clean Water Act)**

This product does not contain any substances regulated as pollutants pursuant to the Clean Water Act (40 CFR 122.21 and 40 CFR 122.42)

**CERCLA**

This material, as supplied, does not contain any substances regulated as hazardous substances under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302) or the Superfund Amendments and Reauthorization Act (SARA) (40 CFR 355). There may be specific reporting requirements at the local, regional, or state level pertaining to releases of this material

**US State Regulations**

**California Proposition 65**

This product does not contain any Proposition 65 chemicals

**U.S. State Right-to-Know Regulations**

**U.S. EPA Label Information**

EPA Pesticide Registration Number Not applicable

**16. OTHER INFORMATION, INCLUDING DATE OF PREPARATION OF THE LAST REVISION**

<b>NFPA</b>	Health hazards 3	Flammability 1	Instability 0	Physical and Chemical Properties -
<b>HMIS</b>	Health hazards 3*	Flammability 1	Physical hazards 0	Personal protection X

Issue Date 29-Sep-2019

Revision Date 29-Sep-2019

**Revision Note**

No information available

**Disclaimer**

The information provided in this Material Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text.

**End of Safety Data Sheet**



# SAFETY DATA SHEET

Issue Date 29-Sep-2019

Revision Date 29-Sep-2019

Version 1

## 1. IDENTIFICATION

### Product identifier

**Product Name** PRODEQ FX400 DARK GREY PART B

### Other means of identification

**Product Code** TQ904DG

**UN/ID no** UN3066

**Synonyms** None

### Recommended use of the chemical and restrictions on use

**Recommended Use** Industrial Coatings

**Uses advised against** No information available

### Details of the supplier of the safety data sheet

#### **Supplier Address**

HENRY COMPANY  
15 Wallsend Dr.  
Scarborough, ON M1E 3X6  
Canada

Web Site: [www.henry.com](http://www.henry.com)  
[www.ca.henry.com](http://www.ca.henry.com)

#### **Manufacturer Address**

HENRY COMPANY  
999 N. Pacific Coast Hwy., Suite 800  
El Segundo, CA 90245-2716  
Web Site: [www.henry.com](http://www.henry.com) [www.ca.henry.com](http://www.ca.henry.com)

### Emergency telephone number

**Company Phone Number** 800-486-1278

**Emergency Telephone** US and Canada only (toll-free) : 3E Company - 1-866-519-4752 (access code 334832)  
US/Canada, all other countries: 3E Company - +1-760-476-3962 (access code 334832)  
Mexico (additional contact option): 3E Company - +52 55 41696225 (Code 334832)

## 2. HAZARDS IDENTIFICATION

### Classification

#### **OSHA Regulatory Status**

This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Acute toxicity - Oral	Category 4
Skin corrosion/irritation	Category 1 Sub-category C
Serious eye damage/eye irritation	Category 1
Skin sensitization	Category 1
Specific target organ toxicity (single exposure)	Category 3
Specific target organ toxicity (repeated exposure)	Category 2

### Label elements

#### **Emergency Overview**

**Danger**

**Hazard statements**

Harmful if swallowed  
Causes severe skin burns and eye damage  
May cause an allergic skin reaction  
May cause respiratory irritation. May cause drowsiness or dizziness  
May cause damage to organs through prolonged or repeated exposure



**Appearance** viscous

**Physical state** liquid

**Odor** Slight Amine

#### **Precautionary Statements - Prevention**

Wash face, hands and any exposed skin thoroughly after handling  
Do not eat, drink or smoke when using this product  
Do not breathe dust/fume/gas/mist/vapors/spray  
Wear protective gloves/protective clothing/eye protection/face protection  
Contaminated work clothing should not be allowed out of the workplace  
Use only outdoors or in a well-ventilated area

#### **Precautionary Statements - Response**

IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing  
Immediately call a POISON CENTER or doctor/physician  
IF ON SKIN (or hair): Remove/Take off immediately all contaminated clothing. Rinse skin with water/shower  
If skin irritation or rash occurs: Get medical advice/attention  
Wash contaminated clothing before reuse  
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing  
Call a POISON CENTER or doctor/physician if you feel unwell  
IF SWALLOWED: Call a POISON CENTER or doctor/physician if you feel unwell  
Rinse mouth  
Do NOT induce vomiting

#### **Precautionary Statements - Storage**

Store locked up  
Store in a well-ventilated place. Keep container tightly closed

#### **Precautionary Statements - Disposal**

Dispose of contents/container to an approved waste disposal plant

#### **Hazards not otherwise classified (HNOC)**

Not applicable

#### **Other Information**

Toxic to aquatic life with long lasting effects. Toxic to aquatic life.

#### **Unknown acute toxicity**

0% of the mixture consists of ingredient(s) of unknown toxicity

### **3. COMPOSITION/INFORMATION ON INGREDIENTS**

#### **Substance**

Not applicable

#### **Mixture**

Chemical Name	CAS No	Weight-%
Polypropylene glycol *	25322-69-4	40 - 70
Diethyltoluenediamine *	68479-98-1	15 - 40
Propylene glycol diamine, 2-amino-, diether with Propylene *	9046-10-0	7 - 13

\*The exact percentage (concentration) of composition has been withheld as a trade secret.

#### 4. FIRST AID MEASURES

##### Description of first aid measures

<b>General advice</b>	Immediate medical attention is required.
<b>Eye contact</b>	Immediately flush with plenty of water. After initial flushing, remove any contact lenses and continue flushing for at least 15 minutes. Keep eye wide open while rinsing. Call a physician immediately.
<b>Skin contact</b>	Immediate medical attention is required. Wash off immediately with soap and plenty of water while removing all contaminated clothes and shoes.
<b>Inhalation</b>	Immediate medical attention is required. Remove to fresh air. If not breathing, give artificial respiration. Avoid direct contact with skin. Use barrier to give mouth-to-mouth resuscitation.
<b>Ingestion</b>	Do NOT induce vomiting. Call a physician or poison control center immediately. Never give anything by mouth to an unconscious person. Drink plenty of water.
<b>Self-protection of the first aider</b>	Use personal protective equipment as required. Avoid contact with skin, eyes or clothing.

##### Most important symptoms and effects, both acute and delayed

<b>Symptoms</b>	May cause redness and tearing of the eyes. Coughing and/ or wheezing. May cause skin irritation. May cause allergic skin reaction.
-----------------	--

##### Indication of any immediate medical attention and special treatment needed

<b>Note to physicians</b>	Treat symptomatically.
---------------------------	------------------------

#### 5. FIRE-FIGHTING MEASURES

##### Suitable extinguishing media

Use extinguishing measures that are appropriate to local circumstances and the surrounding environment. Dry chemical, CO<sub>2</sub>, sand, earth, water spray or regular foam.

**Unsuitable extinguishing media** Do not use a solid water stream as it may scatter and spread fire.

##### Specific hazards arising from the chemical

Thermal decomposition can lead to release of irritating and toxic gases and vapors.

##### Explosion data

**Sensitivity to Mechanical Impact** None.

**Sensitivity to Static Discharge** None.

##### Protective equipment and precautions for firefighters

As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

#### 6. ACCIDENTAL RELEASE MEASURES

##### Personal precautions, protective equipment and emergency procedures

<b>Personal precautions</b>	Use personal protective equipment as required. Keep people away from and upwind of spill/leak.
-----------------------------	--



**Environmental precautions**

**Environmental precautions** Prevent further leakage or spillage if safe to do so. Prevent product from entering drains.

**Methods and material for containment and cleaning up**

**Methods for containment** Prevent further leakage or spillage if safe to do so. Cover powder spill with plastic sheet or tarp to minimize spreading. Dike far ahead of liquid spill for later disposal.

**Methods for cleaning up** Cover liquid spill with sand, earth or other non-combustible absorbent material. Use personal protective equipment as required. Dam up. Take up mechanically, placing in appropriate containers for disposal. Clean contaminated surface thoroughly.

## 7. HANDLING AND STORAGE

**Precautions for safe handling**

**Advice on safe handling** Avoid contact with skin, eyes or clothing. Wash contaminated clothing before reuse. Use personal protective equipment as required. Do not breathe dust/fume/gas/mist/vapors/spray. Do not eat, drink or smoke when using this product.

**Conditions for safe storage, including any incompatibilities**

**Storage Conditions** Keep container tightly closed in a dry and well-ventilated place. Keep out of the reach of children.

**Incompatible materials** Strong oxidizing agents. Strong acids. Strong bases.

## 8. EXPOSURE CONTROLS/PERSONAL PROTECTION

**Control parameters**

**Exposure Guidelines** This product, as supplied, does not contain any hazardous materials with occupational exposure limits established by the region specific regulatory bodies.

**Appropriate engineering controls**

**Engineering Controls** Showers  
Eyewash stations  
Ventilation systems.

**Individual protection measures, such as personal protective equipment**

**Eye/face protection** Tight sealing safety goggles.

**Skin and body protection** Wear protective gloves and protective clothing.

**Respiratory protection** If exposure limits are exceeded or irritation is experienced, NIOSH/MSHA approved respiratory protection should be worn. Positive-pressure supplied air respirators may be required for high airborne contaminant concentrations. Respiratory protection must be provided in accordance with current local regulations.

**General Hygiene Considerations** When using do not eat, drink or smoke. Regular cleaning of equipment, work area and clothing is recommended. Avoid contact with skin, eyes or clothing. Wash hands thoroughly after handling. Keep away from food, drink and animal feeding stuffs.

## 9. PHYSICAL AND CHEMICAL PROPERTIES

**Information on basic physical and chemical properties**

**Physical state** liquid

<b>Appearance</b>	viscous	<b>Odor</b>	Slight Amine
<b>Color</b>	pigmented	<b>Odor threshold</b>	No information available
<b>Property</b>	<b>Values</b>	<b>Remarks • Method</b>	
<b>pH</b>	>10	solution (1 %)	
<b>Melting point / freezing point</b>	No information available		
<b>Boiling point / boiling range</b>	No information available		
<b>Flash point</b>	> 120 °C / 248 °F	Tag Closed Cup	
<b>Evaporation rate</b>	No information available		
<b>Flammability (solid, gas)</b>	No information available		
<b>Flammability Limit in Air</b>			
<b>Upper flammability limit:</b>	No information available		
<b>Lower flammability limit:</b>	No information available		
<b>Vapor pressure</b>	No information available		
<b>Vapor density</b>	>1		
<b>Relative density</b>	0.94		
<b>Water solubility</b>	negligible		
<b>Solubility in other solvents</b>	No information available		
<b>Partition coefficient</b>	No information available		
<b>Autoignition temperature</b>	No information available		
<b>Decomposition temperature</b>	No information available		
<b>Kinematic viscosity</b>	> 100 mm <sup>2</sup> /s	@ 40 °C	
<b>Dynamic viscosity</b>	No information available		
<b>Explosive properties</b>	Not an explosive		
<b>Oxidizing properties</b>	Not applicable		
<b><u>Other Information</u></b>			
<b>Softening point</b>	No information available		
<b>Molecular weight</b>	No information available		
<b>VOC Content (%)</b>	No information available		
<b>Density</b>	No information available		
<b>Bulk density</b>	No information available		

## 10. STABILITY AND REACTIVITY

### Reactivity

No data available

### Chemical stability

Stable under recommended storage conditions.

### Possibility of Hazardous Reactions

None under normal processing.

### Conditions to avoid

Elevated Temperature. Incompatible materials.

### Incompatible materials

Strong oxidizing agents. Strong acids. Strong bases.

### Hazardous Decomposition Products

Thermal decomposition can lead to release of irritating and toxic gases and vapors.

## 11. TOXICOLOGICAL INFORMATION

### Information on likely routes of exposure

#### Product Information

<b>Inhalation</b>	Irritating to respiratory system.
<b>Eye contact</b>	Corrosive to the eyes and may cause severe damage including blindness.
<b>Skin contact</b>	May cause burns. May cause sensitization by skin contact. Harmful in contact with skin.

**Ingestion**

Harmful if swallowed.

Chemical Name	Oral LD50	Dermal LD50	Inhalation LC50
Polypropylene glycol 25322-69-4	= 3750 mg/kg ( Rat ) > 2 g/kg ( Rat )	-	-
Diethyltoluenediamine 68479-98-1	= 472 mg/kg ( Rat ) = 485 mg/kg ( Rat )	= 700 mg/kg ( Rabbit )	-
Propylene glycol diamine, 2-amino-, diether with Propylene 9046-10-0	= 242 mg/kg ( Rat )	= 360 mg/kg ( Rabbit )	-

**Information on toxicological effects****Symptoms**

May cause an allergic skin reaction. Causes skin burns. May cause redness and tearing of the eyes. Coughing and/ or wheezing.

**Delayed and immediate effects as well as chronic effects from short and long-term exposure****Corrosivity**

Risk of serious damage to eyes. Causes burns.

**Sensitization**

May cause sensitization by skin contact.

**Germ cell mutagenicity**

Based on available data, the classification criteria are not met.

**Carcinogenicity**

Based on available data, the classification criteria are not met.

**Reproductive toxicity**

Based on available data, the classification criteria are not met.

**STOT - single exposure**

Target Organs. Respiratory system. Eyes. Skin.

**STOT - repeated exposure**

Causes damage to organs through prolonged or repeated exposure.

**Chronic toxicity**

May cause adverse effects on the bone marrow and blood-forming system. May cause adverse liver effects.

**Target Organ Effects**

blood, Central nervous system, Eyes, kidney, liver, Respiratory system, Skin, Urinary Tract.

**Aspiration hazard**

Based on available data, the classification criteria are not met.

**Numerical measures of toxicity - Product Information**

The following values are calculated based on chapter 3.1 of the GHS document .

ATEmix (oral) 324.00 mg/kg

ATEmix (dermal) 490.00 mg/kg

**12. ECOLOGICAL INFORMATION****Ecotoxicity**

Toxic to aquatic life with long lasting effects

0 % of the mixture consists of component(s) of unknown hazards to the aquatic environment

**Persistence and degradability**

No information available.

**Bioaccumulation**

No information available.

**Other adverse effects**

No information available

**13. DISPOSAL CONSIDERATIONS****Waste treatment methods****Disposal of wastes**

Disposal should be in accordance with applicable regional, national and local laws and regulations.

**Contaminated packaging**

Do not reuse container.

**US EPA Waste Number**

D002

## 14. TRANSPORT INFORMATION

**DOT**

<b>UN/ID no</b>	UN3066
<b>Proper shipping name</b>	Paint
<b>Hazard Class</b>	8
<b>Packing Group</b>	III
<b>Special Provisions</b>	B52, IB3, T4, TP1, TP29
<b>Description</b>	UN3066, Paint, 8, III
<b>Emergency Response Guide Number</b>	153

**TDG**

<b>UN/ID no</b>	UN3066
<b>Proper shipping name</b>	Paint
<b>Hazard Class</b>	8
<b>Packing Group</b>	III
<b>Description</b>	UN3066, Paint, 8, III

**IATA**

<b>UN/ID no</b>	UN3066
<b>Proper shipping name</b>	Paint
<b>Hazard Class</b>	8
<b>Packing Group</b>	III
<b>ERG Code</b>	8L
<b>Special Provisions</b>	A3, A72, A803, A192
<b>Description</b>	UN3066, Paint, 8, III

**IMDG**

<b>UN/ID no</b>	UN3066
<b>Proper shipping name</b>	Paint
<b>Hazard Class</b>	8
<b>Packing Group</b>	III
<b>EmS-No</b>	F-A, S-B
<b>Special Provisions</b>	163, 223
<b>Description</b>	UN3066, Paint, 8, III

## 15. REGULATORY INFORMATION

**International Inventories**

<b>TSCA</b>	Complies
<b>DSL/NDSL</b>	Complies
<b>EINECS/ELINCS</b>	Complies
<b>IECSC</b>	Complies
<b>KECL</b>	Complies
<b>PICCS</b>	Complies
<b>AICS</b>	Complies

**Legend:**

**TSCA** - United States Toxic Substances Control Act Section 8(b) Inventory  
**DSL/NDSL** - Canadian Domestic Substances List/Non-Domestic Substances List  
**EINECS/ELINCS** - European Inventory of Existing Chemical Substances/European List of Notified Chemical Substances  
**ENCS** - Japan Existing and New Chemical Substances  
**IECSC** - China Inventory of Existing Chemical Substances  
**KECL** - Korean Existing and Evaluated Chemical Substances  
**PICCS** - Philippines Inventory of Chemicals and Chemical Substances  
**AICS** - Australian Inventory of Chemical Substances

**US Federal Regulations**

**SARA 313**

Section 313 of Title III of the Superfund Amendments and Reauthorization Act of 1986 (SARA). This product does not contain any chemicals which are subject to the reporting requirements of the Act and Title 40 of the Code of Federal Regulations, Part 372

**SARA 311/312 Hazard Categories**

<b>Acute health hazard</b>	Yes
<b>Chronic Health Hazard</b>	Yes
<b>Fire hazard</b>	No
<b>Sudden release of pressure hazard</b>	No
<b>Reactive Hazard</b>	No

**CWA (Clean Water Act)**

This product does not contain any substances regulated as pollutants pursuant to the Clean Water Act (40 CFR 122.21 and 40 CFR 122.42)

**CERCLA**

This material, as supplied, does not contain any substances regulated as hazardous substances under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302) or the Superfund Amendments and Reauthorization Act (SARA) (40 CFR 355). There may be specific reporting requirements at the local, regional, or state level pertaining to releases of this material

**US State Regulations**

**California Proposition 65**

This product does not contain any Proposition 65 chemicals

**U.S. State Right-to-Know Regulations**

**U.S. EPA Label Information**

EPA Pesticide Registration Number Not applicable

**16. OTHER INFORMATION, INCLUDING DATE OF PREPARATION OF THE LAST REVISION**

<b>NFPA</b>	Health hazards 3	Flammability 1	Instability 0	Physical and Chemical Properties -
<b>HMIS</b>	Health hazards 3*	Flammability 1	Physical hazards 0	Personal protection X

Issue Date 29-Sep-2019

Revision Date 29-Sep-2019


**Revision Note**

No information available

**Disclaimer**

The information provided in this Material Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text.

**End of Safety Data Sheet**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**CURB FLASHING**

**TYPICAL PRODEQ SYSTEM  
UPTURN FLASHING AT CURB**

SCALE: N.T.S.

11-07-2019

**PRODEQ-C4A**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**CURB FLASHING**

**TYPICAL PRODEQ SYSTEM  
UPTURN FLASHING AT CURB WITH TOP OR WEAR COAT**


SCALE: N.T.S.

11-07-2019

**PRODEQ-C4B**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**CURB FLASHING**  
**TYPICAL PRODEQ SYSTEM**  
**UPTURN FLASHING AT WINDOW SILL**

SCALE: N.T.S.

11-07-2019

**PRODEQ-C4E**





**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**CURB FLASHING**

**TYPICAL PRODEQ SYSTEM - UPTURN  
FLASHING AT WINDOW SILL WITH TOP OR WEAR COAT**

SCALE: N.T.S.

11-07-2019

**PRODEQ-C4F**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**CURB FLASHING**

**TYPICAL PRODEQ SYSTEM  
 UPTURN FLASHING AT DOOR THRESHOLD**

SCALE: N.T.S.

11-07-2019

**PRODEQ-C4G**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**CURB FLASHING**

**TYPICAL PRODEQ SYSTEM - UPTURN FLASHING AT DOOR THRESHOLD WITH TOP OR WEAR COAT**


SCALE: N.T.S.

11-07-2019

**PRODEQ-C4H**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**OUTSIDE CORNERS**

**TYPICAL PRODEQ SYSTEM  
CORNER FLASHING AT DOWNTURN**

SCALE: N.T.S.

11-07-2019

**PRODEQ-C7C**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**OUTSIDE CORNERS**

**TYPICAL PRODEQ SYSTEM - CORNER FLASHING AT DOWNTURN WITH TOP OR WEAR COAT**


SCALE: N.T.S.

11-07-2019

**PRODEQ-C7D**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
4. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
5. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.


**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**DRAIN DETAIL**  
**TYPICAL PRODEQ SYSTEM**  
**DRAIN WITH CLAMPING RING**

SCALE: N.T.S.

11-07-2019

**PRODEQ-D1C1**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
4. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
5. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**DRAIN DETAIL**

**TYPICAL PRODEQ SYSTEM  
BI-LEVEL/TWO STAGE DRAIN**


SCALE: N.T.S.

11-07-2019

**PRODEQ-D1C2**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**DRAIN DETAIL**


**TYPICAL PRODEQ SYSTEM WITH WEAR COAT  
DRAIN WITH CLAMPING RING**

SCALE: N.T.S.

11-07-2019

**PRODEQ-D2C1**





**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**DRAIN DETAIL**  
**TYPICAL PRODEQ SYSTEM WITH WEAR COAT**  
**BI-LEVEL/TWO STAGE DRAIN**

SCALE: N.T.S. 11-07-2019

**PRODEQ-D2C2**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.


**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**SCUPPER**  
**TYPICAL PRODEQ SYSTEM**  
**THRU-WALL SCUPPER FLASHING**

SCALE: N.T.S.

11-07-2019

**PRODEQ-D3A**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**SCUPPER**

**TYPICAL PRODEQ SYSTEM - THRU-WALL SCUPPER FLASHING WITH TOP OR WEAR COAT**


SCALE: N.T.S.

11-07-2019

**PRODEQ-D3B**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. EXPANSION JOINT MANUFACTURED AND INSTALLED BY OTHERS AS SPECIFIED. CONTACT HENRY FOR PROJECT SPECIFIC COORDINATION OF **PRODEQ** SYSTEM WITH EXPANSION JOINT.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**EXPANSION JOINT**

**TYPICAL PRODEQ SYSTEM  
PREFABRICATED EXPANSION JOINT**

SCALE: N.T.S.

11-07-2019

**PRODEQ-EJ1**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. EXPANSION JOINT MANUFACTURED AND INSTALLED BY OTHERS AS SPECIFIED. CONTACT HENRY FOR PROJECT SPECIFIC COORDINATION OF **PRODEQ** SYSTEM WITH EXPANSION JOINT.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**EXPANSION JOINT**

**TYPICAL PRODEQ SYSTEM  
PREFABRICATED EXPANSION JOINT WITH WEAR COAT**


SCALE: N.T.S.

11-07-2019

**PRODEQ-EJ4**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FORM A COOL SLEEVE AROUND PIPES HOTTER THAN 150 °F.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**PIPE PENETRATION**

**TYPICAL PRODEQ SYSTEM  
PIPE PENETRATION ON A HORIZONTAL SUBSTRATE**


SCALE: N.T.S.

11-07-2019

**PRODEQ-P1A**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. FORM A COOL SLEEVE AROUND PIPES HOTTER THAN 150 °F.
5. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
6. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
7. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
8. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**PIPE PENETRATION**

**TYPICAL PRODEQ SYSTEM - PIPE PENETRATION ON A HORIZONTAL SUBSTRATE WITH TOP OR WEAR COAT**

SCALE: N.T.S.


11-07-2019

**PRODEQ-P1B**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com





**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FORM A COOL SLEEVE AROUND PIPES HOTTER THAN 150 °F.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**PIPE PENETRATION**


**TYPICAL PRODEQ SYSTEM  
 PIPE PENETRATION ON A VERTICAL SUBSTRATE**

SCALE: N.T.S.

11-07-2019

**PRODEQ-P2A**





**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FORM A COOL SLEEVE AROUND PIPES HOTTER THAN 150 °F.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**PIPE PENETRATION**

**TYPICAL PRODEQ SYSTEM - PIPE PENETRATION  
 ON A VERTICAL SUBSTRATE WITH TOP COAT**

SCALE: N.T.S.

11-07-2019

**PRODEQ-P2B**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. INSTALL MOUNTING COMPONENTS PER MOUNTING PLATE MANUFACTURER REQUIREMENTS. SIZE, PLACEMENT, AND FASTENER HEAD SELECTION AS SPECIFIED. FASTENERS MUST NOT PENETRATE COMPLETELY THROUGH DECK. REMOVE EXCESS THREADS FROM FASTENER AND PEEN INTO PLACE.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**MOUNTING PLATE**

**TYPICAL PRODEQ SYSTEM - MOUNTING PLATE  
INSTALLED DIRECTLY ONTO DECK**


SCALE: N.T.S.

11-07-2019

**PRODEQ-P3A**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. INSTALL MOUNTING COMPONENTS PER MOUNTING PLATE MANUFACTURER REQUIREMENTS. SIZE, PLACEMENT, AND FASTENER HEAD SELECTION AS SPECIFIED. FASTENERS MUST NOT PENETRATE COMPLETELY THROUGH DECK. REMOVE EXCESS THREADS FROM FASTENER AND PEEN INTO PLACE.
5. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
6. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
7. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
8. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**MOUNTING PLATE**

**TYPICAL PRODEQ SYSTEM - MOUNTING PLATE  
INSTALLED ONTO DECK WITH TOP OR WEAR COAT**


SCALE: N.T.S.

11-07-2019

**PRODEQ-P3B**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. INSTALL MOUNTING COMPONENTS PER MOUNTING PLATE MANUFACTURER REQUIREMENTS. SIZE, PLACEMENT, AND FASTENER HEAD SELECTION AS SPECIFIED. FASTENERS MUST NOT PENETRATE COMPLETELY THROUGH DECK. REMOVE EXCESS THREADS FROM FASTENER AND PEEN INTO PLACE.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**MOUNTING PLATE**  
**TYPICAL PRODEQ SYSTEM - MOUNTING PLATE**  
**INSTALLED ON EXISTING PRODEQ SYSTEM**

SCALE: N.T.S. 11-07-2019

**PRODEQ-P3C**



999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. INSTALL MOUNTING COMPONENTS PER MOUNTING PLATE MANUFACTURER REQUIREMENTS. SIZE, PLACEMENT, AND FASTENER HEAD SELECTION AS SPECIFIED. FASTENERS MUST NOT PENETRATE COMPLETELY THROUGH DECK. REMOVE EXCESS THREADS FROM FASTENER AND PEEN INTO PLACE.
5. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
6. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
7. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
8. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**MOUNTING PLATE**

**MOUNTING PLATE INSTALLED ON EXISTING PRODEQ SYSTEM WITH TOP OR WEAR COAT**


SCALE: N.T.S.

11-07-2019

**PRODEQ-P3D**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. DO NOT INSTALL **PRODEQ** SYSTEM OVER SUBSTRATES/AREAS THAT EXCEED MAXIMUM MOISTURE ALLOWANCES. VERIFY CRACKS DO NOT HAVE PERCOLATING MOISTURE. REFER TO **PRODEQ** SYSTEM MOISTURE TEST METHODS TECH-TALK BULLETIN FOR FURTHER INFORMATION.
4. REMOVE EXCESS PRIMER FROM GAP PRIOR TO APPLYING **HENRY PRODEQ FX 400**.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**CRACK TREATMENT**

**TYPICAL PRODEQ SYSTEM  
CRACKS UP TO 1/8" WIDE**


SCALE: N.T.S.

11-07-2019

**PRODEQ-SC5**

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. DO NOT INSTALL **PRODEQ** SYSTEM OVER SUBSTRATES/AREAS THAT EXCEED MAXIMUM MOISTURE ALLOWANCES. VERIFY CRACKS DO NOT HAVE PERCOLATING MOISTURE. REFER TO **PRODEQ** SYSTEM MOISTURE TEST METHODS TECH-TALK BULLETIN FOR FURTHER INFORMATION.
5. REMOVE EXCESS PRIMER FROM GAP PRIOR TO APPLYING **HENRY PRODEQ FX 400**.
6. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
7. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
8. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**CRACK TREATMENT**

**PRODEQ SYSTEM NON-MOVING CRACKS  
UP TO 1/8" WIDE WITH WEAR COAT**

SCALE: N.T.S.

11-07-2019


**PRODEQ-SC6**



FILL BUG HOLES/VOIDS WITH  
CONCRETE REPAIR  
MORTAR/GROUT AND ALLOW TO  
FULLY CURE PRIOR TO  
MEMBRANE APPLICATION

**HENRY PRODEQ FX 400** (100 MILS)

PRIMER (SEE NOTE #2)



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. DO NOT INSTALL **PRODEQ** SYSTEM OVER SUBSTRATES/AREAS THAT EXCEED MAXIMUM MOISTURE ALLOWANCES. VERIFY DEFICIENCIES DO NOT HAVE PERCOLATING MOISTURE. REFER TO **PRODEQ** SYSTEM MOISTURE TEST METHODS TECH-TALK BULLETIN FOR FURTHER INFORMATION.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**SUBSTRATE DEFICIENCY**

**TYPICAL PRODEQ SYSTEM - DEFICIENCIES ON  
VERTICAL SUBSTRATES GREATER THAN 1/4" X 1/4"**

SCALE: N.T.S.

11-07-2019


**PRODEQ-SC7**



FILL BUG HOLES/VOIDS WITH  
CONCRETE REPAIR  
MORTAR/GROUT AND ALLOW TO  
FULLY CURE PRIOR TO  
MEMBRANE APPLICATION

**HENRY PRODEQ FX 400** (100 MILS)

PRIMER (SEE NOTE #2)



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. DO NOT INSTALL **PRODEQ** SYSTEM OVER SUBSTRATES/AREAS THAT EXCEED MAXIMUM MOISTURE ALLOWANCES. VERIFY DEFICIENCIES DO NOT HAVE PERCOLATING MOISTURE. REFER TO **PRODEQ** SYSTEM MOISTURE TEST METHODS TECH-TALK BULLETIN FOR FURTHER INFORMATION.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**SUBSTRATE DEFICIENCY**

**DEFICIENCIES ON VERTICAL SUBSTRATES  
GREATER THAN 1/4" X 1/4" WITH TOP COAT**

SCALE: N.T.S.

11-07-2019

**PRODEQ-SC8**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**SUBSTRATE TERMINATIONS**

**TYPICAL PRODEQ SYSTEM  
 TERMINATION ON A VERTICAL SUBSTRATE**

SCALE: N.T.S.

11-07-2019

**PRODEQ-T1C**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**SUBSTRATE TERMINATIONS**

**TYPICAL PRODEQ SYSTEM - TERMINATION  
 ON A VERTICAL SUBSTRATE WITH TOP COAT**

SCALE: N.T.S.

11-07-2019

**PRODEQ-T1D**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
4. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
5. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
 El Segundo, CA 90245  
 800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**


**SUBSTRATE TERMINATIONS**

**TYPICAL PRODEQ SYSTEM  
 TERMINATION ON HORIZONTAL SUBSTRATES**

SCALE: N.T.S.

11-07-2019

**PRODEQ-T2C**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND/OR PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**SUBSTRATE TERMINATIONS**

**TYPICAL PRODEQ SYSTEM WITH WEAR COAT  
TERMINATION ON HORIZONTAL SUBSTRATES**


SCALE: N.T.S.

11-07-2019

**PRODEQ-T2D**

**HENRY PRODEQ SYSTEM  
SEQUENCE OF INSTALLATION**

- ① DECK/SUBSTRATE AS SPECIFIED
- ② PRIMER (SEE NOTE #2)
- ③ WATERPROOFING MEMBRANE:  
**HENRY PRODEQ FX 400 (100 MILS)**



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. REFER TO DETAILS PRODEQ-WB, PRODEQ-WC, OR PRODEQ-WD FOR LONG-TERM COLOR STABILITY, HEAVY CONSTRUCTION TRAFFIC OR ASSEMBLIES WHERE OVERBURDEN BONDS DIRECTLY TO **PRODEQ** SYSTEM .
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**SYSTEM DETAIL**

**TYPICAL PRODEQ SYSTEM  
NO WEAR COAT OR COLOR STABLE TOP COAT**

SCALE: N.T.S.


11-06-2019

**PRODEQ-WA**

**HENRY PRODEQ SYSTEM  
SEQUENCE OF INSTALLATION**

- ① DECK/SUBSTRATE AS SPECIFIED
- ② PRIMER (SEE NOTE #2)
- ③ WATERPROOFING MEMBRANE:  
**HENRY PRODEQ FX 400** (100 MILS)
- ④ COLOR STABLE TOP COAT:  
4A - **HENRY GP TOPCOAT** (10 MILS)  
4B - **HENRY GP TOPCOAT** (10 MILS)

NOTE: INSTALL OPTIONAL **HENRY GP TOPCOAT** AT AREAS EXPOSED TO INDEFINITE UV WHEN LONG-TERM COLOR STABILITY IS DESIRED.



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
4. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
5. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
6. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**SYSTEM DETAIL**

**TYPICAL PRODEQ SYSTEM  
WITH COLOR STABLE TOP COAT**


SCALE: N.T.S.

11-07-2019

**PRODEQ-WB**

**HENRY PRODEQ SYSTEM  
SEQUENCE OF INSTALLATION**

- ① DECK/SUBSTRATE AS SPECIFIED
- ② PRIMER (SEE NOTE #2)
- ③ WATERPROOFING MEMBRANE:  
**HENRY PRODEQ FX 400** (100 MILS)
- ④ WEAR COAT:  
4A - **HENRY GP WEARCOAT** (26 MILS)  
4B - DRY SILICA SAND (SEE NOTE #3)



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**SYSTEM DETAIL**

**TYPICAL PRODEQ SYSTEM  
WITH WEAR COAT**

SCALE: N.T.S.


11-07-2019

**PRODEQ-WC**



**HENRY PRODEQ SYSTEM  
SEQUENCE OF INSTALLATION**

- ① DECK/SUBSTRATE AS SPECIFIED
- ② PRIMER (SEE NOTE #2)
- ③ FLASHING:  
**HENRY PRODEQ FX 400** (40 MILS)
- ④ WATERPROOFING MEMBRANE:  
**HENRY PRODEQ FX 400** (100 MILS)
- ⑤ WEAR COAT (100 MILS)  
5A - **HENRY GP WEARCOAT** (26 MILS)  
5B - DRY SILICA SAND (SEE NOTE #3)
- ⑥ COLOR STABLE TOP COAT:  
6A - **HENRY GP TOPCOAT** (10 MILS)  
6B - **HENRY GP TOPCOAT** (10 MILS)



**NOTES:**

1. DETAIL SHOWS HENRY **PRODEQ** SYSTEM WATERPROOFING ASSEMBLY. SUBSTRATE SHOWN IS FOR REFERENCE ONLY. REFER TO PRODUCT SPECIFIC TECHNICAL DATA SHEET FOR AUTHORIZED SUBSTRATES.
2. THE STANDARD PRIMER FOR THE HENRY **PRODEQ** SYSTEM IS **HENRY ST PRIMER** WITH AGGREGATE. OTHER RECOMMENDED PRIMERS INCLUDE: **HENRY LV PRIMER**, **HENRY STXL PRIMER** WITH AGGREGATE, **PUMADEQ PRIMER 20** WITH AGGREGATE AND **HENRY GC EPOXY PRIMER**. REFER TO PRODUCT SPECIFIC DATA SHEET FOR PRODUCT SPECIFIC INFORMATION.
3. FULLY BROADCAST, TO REJECTION, DRY SILICA SAND (SIEVE SIZE: #20-30) INTO WET **HENRY GP WEARCOAT**.
4. PREPARE AND PRIME VERTICAL SUBSTRATES A MINIMUM 2" BEYOND **PRODEQ** SYSTEM APPLICATION IN ACCORDANCE WITH HENRY **PRODEQ** SYSTEM SUBSTRATE PREPARATION GUIDELINES TECH-TALK BULLETIN.
5. DO NOT INSTALL **PRODEQ** SYSTEM BEYOND PRIMED SURFACES.
6. HENRY OFFERS PAVERS, RIGID INSULATION, AND PREFABRICATED DRAINAGE COMPOSITES AS A SINGLE SOURCE WARRANTY OPTION PER PROJECT SPECIFIC REQUIREMENTS (NOT SHOWN FOR CLARITY). CONTACT HENRY FOR SYSTEM CONFIGURATIONS AND WARRANTY OPTIONS.
7. REFER TO **PRODEQ** SYSTEM GUIDE SPECIFICATION FOR RECOMMENDED INSTALLATION PROCEDURES.

**Henry**<sup>®</sup>

999 N. Pacific Coast Highway, Suite 800  
El Segundo, CA 90245  
800-486-1278 • www.henry.com

MANUFACTURER GUIDE DETAILS ARE FOR REFERENCE ONLY. HENRY DOES NOT ASSUME RESPONSIBILITY FOR ERRORS OR DEVIATIONS IN DESIGN OR ENGINEERING. PROJECT SPECIFIC VERIFICATION IS RECOMMENDED PRIOR TO INSTALLATION.

**PRODEQ SYSTEM - WATERPROOFING ASSEMBLY**

**SYSTEM DETAIL**  
**TYPICAL PRODEQ SYSTEM**  
**WITH WEAR COAT AND TOP COAT**

SCALE: N.T.S.

11-07-2019

**PRODEQ-WD**

Warranty #: SAMPLE

Issued:

Exclusion:

**HENRY COMPANY ("HENRY")  
5 YEAR EXTENDED MATERIAL WARRANTY  
PRODEQ™ ("PRODUCT")**

Building Name:  
Building Location:  
Building OWNER: ("OWNER")  
Date Product(s) Installation Completed:  
Contractor:  
Square Footage:

---

**What This Limited Warranty Covers:**

Commencing with the date of completion of installation of the Product(s) and continuing for the duration of this Warranty, if manufacturing defects in the Product(s) cause the Product(s) to not perform in conformance with the Product(s) label or tech data sheet, as published on [www.henry.com](http://www.henry.com) at time of warranty issuance, or for its intended application, then HENRY at its sole option will, subject to the following section (What This Warranty Does Not Cover), either (1) refund OWNER's original purchase price for the Product(s) prorated by the unused portion of the warranty term; or (2) provide the amount of Product(s) necessary to make repairs. Under option (1), during the first year after installation of the Product(s), HENRY will refund OWNER's purchase price for the Product(s), exclusive of installation cost and minus any proration and costs previously incurred by HENRY for the replacement of Product(s) under this Warranty. After the first year, the purchase price to be refunded will be prorated by the remaining number of years of the Warranty term, minus any cost previously incurred by HENRY for the replacement of Product(s) under this Warranty.

Decisions as to the extent of repair or replacement required will be made solely by HENRY. The opinion of HENRY with respect to this matter shall be final. The remedy under this Warranty is available only for that portion of the Product(s) exhibiting defects at the time of the warranty claim. The replacement Product(s) as well as any remaining original Product(s) will be warranted only for the original warranty period. This limited warranty applies only to Product(s) used for an application specified by HENRY for the Product(s) and applied in strict accordance with HENRY published specifications, as published on [www.henry.com](http://www.henry.com) in effect at the time of application. IF PRODUCT(S) IS USED FOR OTHER THAN A HENRY SPECIFIED APPLICATION, MISUSED OR ABUSED, IT IS SOLD AS IS AND WITHOUT ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE.

**What This Warranty Does Not Cover:**

This Warranty warrants that the Product(s) will be free from manufacturing defects which affect the ability of the Product(s) to perform in conformance with the Product(s) label or tech data sheet for its intended application during the Warranty Period; it is not a warranty that the Product(s) will never leak or age or to undertake responsibilities, liabilities or obligations other than those specifically identified in the preceding section.

The Contractor who installs the Product(s) is not a representative, agent or employee of HENRY. HENRY therefore is not bound by any representations made by the Contractor and does not warrant or guarantee the Contractor's workmanship.

HENRY is not responsible or liable for: (a) personal injury or property damage of any kind, even if arising from a breach of this Warranty, (b) damage to the building, or to other components of the building or its contents, including mold, mildew or interruption or complete disruption in the use of the building, (c) expenses associated with installation, removal, excavation, or replacement of other materials, building assemblies, mechanical equipment or scaffolding in connection with accessing, testing, repairing, removal, or replacement of the Product(s), (d) change in color or other aesthetic diminution, and (e) damage to the Product(s) attributable to one or more of the following conditions:

1. Acts of God and natural calamities (including, but without limitation, lightning, Beaufort Scale 10 or higher winds, hurricane, tornado, hail, earthquake, flood, or other violent storm or casualty), impact of objects or damage to the Product(s) due to settlement, distortion, failure or cracking of the roof deck, walls or foundation of the building, or for any splitting, cracking, blistering, delamination or separation of the Product(s) due to defect and/or failure of underlying materials not supplied by HENRY or for damage by foot traffic.
2. Civil insurrection, war, riot, terrorism, intentional destruction or vandalism.
3. Exposure to ionized radiation, contamination by radioactivity from any nuclear source, or bird droppings, chemical, or vermin attack on the Product(s).
4. Failure to timely report leaks or to repair leaks not covered by this Warranty.
5. Leaks caused by water entering from building components adjacent to the Product(s) or moisture migration either through or around other building components such as rooftop equipment, walls, copings, pitch pans and details which do not conform with HENRY details.
6. Installations on or through the Product(s) unless done in a manner prescribed and accepted by HENRY.
7. Repairs or alterations to the Product(s) that are not authorized first in writing by HENRY.
8. Normal wear and tear.
9. Any actions or cost resulting from Prodeq smell during application.
10. Discoloration, cleanliness, fading or appearance due to substrate surface profile, normal weathering, dirt and atmospheric pollutants.
11. Leaks due to residual water beneath Prodeq installation, or from another part of the building where Prodeq has not been installed.
12. Vapor drive and moisture vapor transmission from the substrate, not made clear to HENRY, in writing, before Prodeq installation.
13. Damage caused by installation or removal of overburden.
14. Defects in the design, materials, construction or movement of the substrate or structure.
15. Any defects, damage or failure arising as a result of work or activity on Prodeq by others, animals, wind launched debris, sharp or abrasive objects, fire or other causes beyond the control of HENRY.
16. Any building conditions not meeting ASTM C836 parameters.

**Obtaining Warranty Service:**

If the Product(s) fails to perform in conformance with the Product(s) label or tech data sheet for its intended application, notify HENRY by email at [warranty@henry.com](mailto:warranty@henry.com), within 48 hours or within the next business day after discovery of any defect in the Product(s). The OWNER must give written notice to HENRY no later than thirty (30) days after a defect is discovered or should by reasonable diligence have been discovered. Claims under this Warranty will require proof of purchase by the OWNER. HENRY is not responsible for any claims without such proof of purchase. A purchase receipt or other proof of date of original purchase is required before warranty service is provided. Should the alleged failure or the remedy sought by the OWNER lie outside the scope of this Warranty, OWNER agrees to promptly reimburse HENRY for the cost of any investigation requested by OWNER, including remedy costs, plus a HENRY administrative fee of \$250.00.

**Time for Remedy:**

HENRY shall have forty-five (45) days after receipt of written notification of a Product(s) defect to initiate either of the remedies contained in this

Warranty unless prevented by acts of God or events beyond HENRY's reasonable control.

**Limitations and Exclusions:**

TO THE EXTENT PERMITTED BY APPLICABLE LAW, HENRY DISCLAIMS ANY OTHER WARRANTY EXPRESS OR IMPLIED, THAN THAT PROVIDED FOR HEREIN. THIS WARRANTY IS IN LIEU OF AND EXCLUDES ALL OTHER WARRANTIES, GUARANTEES, CONDITIONS AND REPRESENTATIONS, EXPRESS OR IMPLIED, ORAL OR WRITTEN, STATUTORY OR OTHERWISE, INCLUDING BUT NOT LIMITED TO ANY IMPLIED CONDITIONS OR WARRANTIES AS TO THE MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE OF THE HENRY PRODUCT(S). SOME STATES DO NOT ALLOW LIMITATIONS ON HOW LONG AN IMPLIED WARRANTY LASTS, SO THE ABOVE LIMITATION MAY NOT APPLY TO YOU. HENRY DOES NOT AUTHORIZE ANY PERSON INCLUDING ITS REPRESENTATIVES, TO MAKE ANY REPRESENTATION OR TO OFFER ANY WARRANTY, CONDITION OR GUARANTY IN RESPECT OF THE PRODUCT(S) OTHER THAN THIS WARRANTY. THIS MATERIAL WARRANTY CANNOT BE MODIFIED EXCEPT IN WRITING SIGNED BY HENRY'S WARRANTY MANAGER. THIS LIMITED WARRANTY SHALL BE THE OWNER'S SOLE AND EXCLUSIVE REMEDY AGAINST HENRY AND UNDER NO CIRCUMSTANCES SHALL HENRY BE LIABLE FOR AN AMOUNT GREATER THAN THE ACTUAL PURCHASE PRICE OF THE UNIT OR FOR ANY CONSEQUENTIAL, EXEMPLARY, SPECIAL, INCIDENTAL OR OTHER DAMAGES INCLUDING, BUT NOT LIMITED TO, LOSS OF PROFITS, LOSS OF USE, OR DAMAGE TO THE BUILDING OR ITS CONTENTS OR THE ROOF DECK. INCIDENTAL, CONSEQUENTIAL AND EXEMPLARY DAMAGES SHALL NOT BE RECOVERABLE EVEN IF THE REMEDIES OR THE ACTIONS PROVIDED FOR IN THIS WARRANTY FAIL OF THEIR ESSENTIAL PURPOSE. SOME STATES DO NOT ALLOW THE EXCLUSION OR LIMITATION OF INCIDENTAL OR CONSEQUENTIAL DAMAGES, SO THE ABOVE LIMITATION OR EXCLUSION MAY NOT APPLY TO YOU. HENRY SHALL NOT BE LIABLE FOR ANY DAMAGES WHICH ARE BASED UPON NEGLIGENCE, GROSS NEGLIGENCE, BREACH OF WARRANTY, BREACH OF CONTRACT, STRICT LIABILITY OR ANY OTHER LEGAL THEORY OF LIABILITY OTHER THAN THE EXCLUSIVE LIABILITY SET FORTH IN THIS WARRANTY.

**Conditions of Warranty:**

HENRY's continuing liability under this Warranty is conditioned upon the following:

- a) The SYSTEM must terminate higher than any possible water level;
- b) The Product(s) was stored, handled, applied and maintained in accordance with HENRY's instructions, recommendations and specifications in effect at the time of application;

- c) The Product(s) and all components thereof have been sold by HENRY except where authorized by HENRY;
- d) HENRY and the Contractor have been paid in full for the Product(s) including but not limited to installation and equipment rental;
- e) The Product(s) has not been altered, modified or repaired without prior written approval of HENRY;
- f) The OWNER has notified HENRY in writing of any failure of the Product(s) covered by this Warranty within thirty (30) days following such failure;
- g) There has been no misuse, abuse or negligence with respect to the Product(s) on the part of the OWNER, facility or mechanical tradesmen.

**Transfer:**

This Warranty is assignable conditioned upon prior written approval by HENRY. Such approval is subject to the terms, conditions and fees contained in HENRY's application for transfer of warranty.

**Waiver:**

HENRY's failure at any time to enforce or rely upon any of the terms or conditions stated herein shall not be construed to be a waiver of its rights hereunder.

**OWNER's Agreement:**

HENRY would not agree to assume the obligations contained in this Warranty in the absence of any of the limitations and exclusions contained herein. Therefore, (1) OWNER's agreement to each and every term of this Warranty is an essential condition precedent to HENRY's obligations hereunder; (2) in the absence of such agreement by the OWNER the Product(s) is sold AS IS AND WITHOUT ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE; (3) failure of any condition precedent herein shall discharge HENRY from all further obligation under this Warranty, and the disclaimer herein of any other warranties, conditions and representations shall survive; and (4) by accepting or asserting any rights hereunder, OWNER irrevocably agrees to indemnify and hold harmless HENRY, its affiliates, successors, assigns, directors, officers, employees and agents (each an "Indemnified Party") from and against all claims, expenses (including attorney's fees and expenses), losses, liabilities and damages in any way related to or arising from matters described in the section of this Warranty entitled "What This Warranty Does Not Cover," and all amounts paid in defense of the foregoing which may be imposed upon, incurred by or asserted against an Indemnified Party by any person, firm or entity.

Except as otherwise expressly provided above, this Warranty shall be governed by and construed in accordance with the laws of the State of Texas without regard to conflict of law rules.

---

THIS WARRANTY GIVES YOU SPECIFIC LEGAL RIGHTS, AND YOU MAY ALSO HAVE OTHER RIGHTS WHICH VARY FROM STATE TO STATE OR COUNTRY TO COUNTRY, IF OUTSIDE OF THE UNITED STATES.

**HENRY COMPANY**

By: \_\_\_\_\_  
Name:

Date: \_\_\_\_\_

**NOTE: SAMPLE WARRANTIES ARE PROVIDED CONDITIONALLY AND SHOULD NOT BE CONSTRUED OR INTERPRETED AS A REPRESENTATION OR PROMISE THAT HENRY WILL IN FACT PROVIDE SUCH A WARRANTY FOR A SPECIFIC PROJECT. HENRY WARRANTIES ARE NOT VALID OR BINDING UNLESS AND UNTIL ALL OF HENRY'S REQUIREMENTS FOR WARRANTY ISSUANCE ARE MET AND A PROJECT-SPECIFIC WARRANTY IS ISSUED. HENRY RESERVES THE RIGHT TO MODIFY THE TERMS OF ITS SAMPLE WARRANTIES FOR ANY REASON, AT ANYTIME, WITH OR WITHOUT NOTICE. FOR MORE INFORMATION ABOUT HENRY'S REQUIREMENTS, PLEASE CONTACT THE HENRY WARRANTY DEPARTMENT AT [WARRANTY@HENRY.COM](mailto:WARRANTY@HENRY.COM).**

## Product Certification

### Henry® Prodeq™ Waterproofing Membrane (FX400)

Prodeq is a 2-part, spray-applied, seamless polyurethane hybrid membrane that is instant setting.

Prodeq meets the following:

- ASTM C836
- Crack Bridging per ASTM C1305

Prodeq is compatible with the following commonly used Henry products:

- Pumadeq Primers (incl. ST, LV, STXL, Primer 20, GC)
- GP Wearcoat
- FX Activator
- Duratac Self-Adhered Membrane
- NP180 Modbit Membranes
- Pumadeq Flex 30SL
- Pumadeq Flex 31MV
- Pumadeq Flex 32TX

Prodeq is compatible with cast-in-place and precast normal weight concrete, lightweight structural concrete, modified bitumen sheet membrane, CMU, steel, stainless steel, aluminum, galvanized metal, copper, rigid PVC, dimensional lumber and plywood.

Prodeq can be used on all slopes ranging from vertical to dead level including fully submerged water conditions.

Prodeq has 0 g/L VOC content

Henry Company production facilities maintain and adhere to a full-time quality control program.

Physical properties and application instructions are available on Henry technical data sheets viewable at [www.henry.com](http://www.henry.com). or upon request.

## LEED Certification

**PRODUCT:**                      **FX 400**

**MR - CREDIT 4.x – RECYCLED CONTENT**

RECYCLED CONTENT (POST-CONSUMER):                      0%  
RECYCLED CONTENT (POST-INDUSTRIAL):                      0%

**MR - CREDIT 5.x– REGIONAL MATERIALS**

**EXTRACTION SITE:**                      Raw materials are sourced to Henry from various North American sources and extraction site of raw materials may vary without notice. As a result, the extraction site of materials used to manufacture this product is undetermined.

**MANUFACTURING SITE:**                      23 Commerce Rd, Fairfield, NJ 07004

**VOC CONTENT:**                      0 g/L calculated less water